

Alamo Colleges WFAC Black Box Addition PKG 1

1801 Martin Luther King Dr.,
San Antonio, TX, 78203

ISSUE FOR CONSTRUCTION

2024/06/14



BOARD OF TRUSTEES

JOE ALDERETE JR.
GLORIA RAY
ANNA URIEGAS BUSTAMANTE
DR. LORENA PULIDO
ROBERTO ZÁRATE
DR. GENE SPRAGUE
DR. YVONNE KATZ
CLINT KINGSBERY
LESLIE SACHANOWICZ
BRANDON AVIADO

DISTRICT 1
ASSISTANT SECRETARY, DISTRICT 2
DISTRICT 3
SECRETARY, DISTRICT 4
DISTRICT 5
DISTRICT 6
DISTRICT 7
VICE CHAIR, DISTRICT 8
DISTRICT 9
STUDENT TRUSTEE

ADMINISTRATION

DR. ADENA WILLIAMS LOSTON
RANDALL DAWSON
WESLEY B. WELLS
GEORGE H. JOHNSON, III
CHRISTOPHER METSGAR
DR. KIMBERLEY IRVING-CONAWAY
DR. DIANE GAVIN
MARSHA P. HALL

PRESIDENT
VICE-PRESIDENT FOR ACADEMIC SUCCESS
VICE-PRESIDENT FOR STUDENT SUCCESS
INTERIM VICE-PRESIDENT FOR COLLEGE
DEAN FOR ACADEMIC SUCCESS, HEALTH SCIENCES
DEADN FOR ACADEMIC SUCCESS, ACADEMIC SERVICES
DEAN OF PERFORMANCE EXCELLENCE
DIRECTOR OF STRATEGIC INITIATIVES

ARCHITECT
PBK ARCHITECTS, INC
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

ASSOCIATE ARCHITECT
B&A ARCHITECTS
222 Ridgcrest Dr
San Antonio, TX 78209
T 210-829-1898

CIVIL ENGINEER
GESSNER
401 W. 26th St, Ste 3
Bryan, TX 77803
T 979-680-8840

STRUCTURAL ENGINEER
LUNDY & FRANKE ENGINEERING
549 Helmer
San Antonio, TX 78232
T 210-979-7900

LANDSCAPE ARCHITECT
EDGELAND GROUP
11 Greenway Plaza, 15th Floor
Houston, TX 77046
T 713-460-0988

MEP ENGINEER
LEAF
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

THEATER CONSULTANT
WJHW
12175 Network Blvd., Suite 150
San Antonio, TX, 78249
T 210-561-9800

ENVELOPE CONSULTANT
BEAM PROFESSIONALS
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

WFAC Black Box Addition PKG 1

1801 Martin Luther King Dr.,
San Antonio, TX, 78203
ISSUE FOR CONSTRUCTION

Table with columns SHEET NUMBER and SHEET NAME. Lists architectural, mechanical, and plumbing sheets including general information, site plans, and details.

ADD ALTERNATES

- 1. PROVIDE SEPARATE PRICING TO REMOVE THE LOBBY ADDITION IN FRONT OF THE EXISTING WATSON THEATER ENTRANCE. THIS IS TO INCLUDE PIERS, FOUNDATION.
2. MUD SLAB:
2A - PROVIDE SEPARATE PRICING TO REMOVE MUD SLAB DOWN TO A PATHWAYS FROM THE FLOOR HATCH TO THE PLUMBING DRAINS. REFER TO SHEET A-100.
2B - PROVIDE SEPARATE PRICING TO REMOVE THE MUD SLAB.

ABBREVIATIONS AND LEGEND KEYS

Table of abbreviations and legend keys. Includes sections for 'REFER TO SCHEDULES AND LEGENDS FOR ADDITIONAL ABBREVIATIONS', 'PROJECT GRAPHIC REFERENCES', and 'CONSTRUCTION TYPE SYMBOLS'. Lists various materials and construction types with their corresponding symbols.

GENERAL NOTES

- A. THE CONTRACT DOCUMENTS ARE TO INCLUDE AIA DOCUMENT A201 "GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION". CLIENT SHALL BE DESIGNATED AS "THE OWNER".
B. THE WORK SHALL BE DONE IN ACCORDANCE WITH THE RULES AND REGULATIONS OF ALL APPLICABLE SAFETY AND BUILDING CODES.
C. CONTRACTOR SHALL REVIEW AND VERIFY EXISTING CONDITIONS AS PROVIDED IN THE CONSTRUCTION DOCUMENTS.
D. CONTRACTOR SHALL BE RESPONSIBLE FOR AND PROVIDE PROTECTION OF ANY EXISTING FINISHES, MATERIALS, AND EQUIPMENT TO REMAIN.
E. ALL MATERIALS AND SYSTEMS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
F. ONLY NEW MATERIALS AND EQUIPMENT OF RECENT MANUFACTURE, OF STANDARD QUALITY, AND FREE FROM DEFECTS, WILL BE PERMITTED IN THE WORK.
G. DO NOT SCALE DRAWINGS. STATED & WRITTEN DIMENSIONS GOVERN.
H. CONTRACTOR SHALL VERIFY THAT NO CONFLICTS EXIST BETWEEN THE LOCATIONS OF EXISTING AND PROPOSED NEW MECHANICAL, ELECTRICAL, PLUMBING, DATA, AND SPRINKLER EQUIPMENT.
I. CONTRACTOR SHALL PROVIDE THE ARCHITECT WITH SHOP DRAWINGS FOR REVIEW AND APPROVAL FOR ALL, BUT NOT LIMITED TO, THE FOLLOWING: SHOP-FABRICATED MILLWORK, CARPET LAYOUT, FLOORING, LIGHT FIXTURES, DOORS, MISC. STEEL, METAL FABRICATION, GLASS/GLAZING, SPRINKLER LAYOUTS, HARDWARE.
J. CONTRACTOR SHALL REVIEW AND COORDINATE THE SIZE AND LOCATION OF ALL SLAB OPENINGS WITH ALL RELATED DISCIPLINES.
K. CONTRACTOR SHALL PROVIDE THE ARCHITECT WITH MANUFACTURER'S CUT SHEETS AND SPECIFICATIONS FOR ALL EQUIPMENT INCLUDING BUT NOT LIMITED TO LIGHT FIXTURES, PLUMBING EQUIPMENT, ELECTRICAL EQUIPMENT, FANS, SUPPLEMENTARY HEATING AND COOLING ELEMENTS, ALL HARDWARE AND SECURITY EQUIPMENT.
L. CONTRACTOR SHALL NOT PROCEED WITH WORK FOR WHICH ADDITIONAL COMPENSATION BEYOND THE CONTRACT AMOUNT IS EXPECTED WITHOUT WRITTEN AUTHORIZATION FROM THE ARCHITECT AND OWNER.
M. CONTRACTOR SHALL REVIEW AND COORDINATE THE SIZE AND LOCATION OF ALL SLAB OPENINGS WITH ALL RELATED DISCIPLINES.
N. PATCH, REPAIR, AND INSTALL ALL FIREPROOFINGS AS REQUIRED BY CODE. FIREPROOF ALL NEW PENETRATIONS AS REQUIRED FOR APPROVAL BY THE AUTHORITY HAVING JURISDICTION.
O. CONTRACTOR SHALL CONTINUOUSLY CHECK ARCHITECTURAL AND STRUCTURAL CLEARANCES FOR ACCESSIBILITY OF EQUIPMENT AND MECHANICAL AND ELECTRICAL SYSTEMS.
P. FINISHED WORK SHALL BE FIRM, WELL-ANCHORED, IN TRUE ALIGNMENT, PLUMB, LEVEL, WITH SMOOTH, CLEAN, UNIFORM APPEARANCE WITHOUT WAVES, DISTORTIONS, HOLES, MARKS, CRACKS, STAINS, OR DISCOLORATION.
Q. ATTACHMENTS, CONNECTIONS OR FASTENERS OF ANY NATURE ARE TO PROPERLY AND PERMANENTLY BE SECURED IN CONFORMANCE WITH INDUSTRY BEST PRACTICES.
R. CONTRACTOR SHALL WAIVE "COMMON PRACTICE" AND "COMMON USAGE" AS CONSTRUCTION CRITERIA WHEREVER DETAILS AND CONTRACT DOCUMENTS OR GOVERNING CODES, ORDINANCES, ETC. REQUIRE QUANTITY OR BETTER QUALITY THAN COMMON PRACTICE OR COMMON USAGE WOULD REQUIRE.
S. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND SUBMITTALS AND SHALL ORDER AND SCHEDULE DELIVERY OF MATERIALS TO AVOID DELAYS IN CONSTRUCTION.
T. CONTRACTOR SHALL NOTIFY THE ARCHITECT IMMEDIATELY WITH A PROPOSED ALTERNATIVE.
U. UNREPORTED DEFICIENCIES WILL BECOME THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO CORRECT.
V. CONTRACTOR SHALL EXERCISE INDUSTRY BEST PRACTICES FOR CARE AND CAUTION DURING THE CONSTRUCTION OF THE WORK AND SHALL SCHEDULE WORK TO MINIMIZE DISTURBANCES TO OCCUPANTS.
W. ADJACENT SPACES AND/OR STRUCTURES, PROPERTY, PUBLIC THOROUGHFARES, ETC. THE GENERAL CONTRACTOR SHALL TAKE PRECAUTIONS AND BE RESPONSIBLE FOR THE SAFETY OF ALL BUILDING OCCUPANTS DURING CONSTRUCTION PROCEDURES.
X. ALL DEBRIS SHALL BE REMOVED FROM THE SITE ON A DAILY BASIS, OR AS DIRECTED BY THE AUTHORITY HAVING JURISDICTION.
Y. ALL ABANDONED AND MISCELLANEOUS NAILS, HANGERS, STAPLES, WIRES, CONDUITS AND DEBRIS SHALL BE REMOVED FROM EXPOSED AREAS OF THE FLOORS, WALLS, AND CEILINGS.
Z. CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY ACCESS PANELS WHICH MAY BE REQUIRED PRIOR TO PROCEEDING WITH THE WORK.
ZB. CONTRACTOR SHALL PROVIDE THE TEAM WITH A CONSTRUCTION SCHEDULE SHOWING THE PROPOSED PHASING. LONG LEAD ITEMS THAT WILL AFFECT THE SUBSTANTIAL COMPLETION DATE SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY.



Table listing project team members and roles: ARCHITECT (SAN ANTONIO), PBK Architects, Inc., SAN ANTONIO, 601 N.W. Loop 410, Suite 400, San Antonio, TX 78216.

Table listing project team members and roles: ARCHITECT (SAN ANTONIO), PBK Architects, Inc., SAN ANTONIO, 601 N.W. Loop 410, Suite 400, San Antonio, TX 78216.

WFAC Black Box Addition PKG 1
1801 Martin Luther King Dr., San Antonio, TX, 78203
ISSUE FOR CONSTRUCTION





Table with columns CLIENT, DATE, PROJECT NUMBER, DRAWING HISTORY (No., Description, Date).



ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

GENERAL PROJECT INFORMATION


G-002

VICINITY MAP






24 TEXAS ACCESSIBILITY STANDARDS
1/4" = 1'-0"



12 ACCESSIBILITY - AGES 13 THRU ADULT (GRADES 8 AND ABOVE)
1/4" = 1'-0"



DESCRIPTION	AGES 13 - ADULT (GRADES 8 AND ABOVE)
WATER CLOSET - To Top of Seat	17" - 19"
Grab Bar Height	33" - 36"
Flush Control Height	25" TYP 44" MAX
URINAL - Max. To Rim of Basin	17"
Knee Clearance (Min)	44"
LAVATORIES: Front Approach	27"
Knee Clearance (Min)	27"
To Top (Max)	34"
To Faucet (Max)	29"
FIXED OR BUILT-IN: Height of Tables or Counter	28" - 34"
Knee Clearance (Min)	27"
SHELVES, DISPENSERS: Max. Height to Control Device	48"
Frontal Approach (Max)	48"
Side Approach (Max)	48"
DRINKING FOUNTAINS: To Spout (Max)	36"
Knee Clearance (Min)	27"
SWITCHES AND CONTROLS: Frontal Approach (Max)	48"
Side Approach (Max)	48"
MIRRORS: Max. Height to Bottom of Reflective Surface	40"
At Lavatories and Counter Tops	35"
Full Length	40"
MIRRORS: Min. Height to Top of Reflective Surface	74"
Full Length	74"
TOILET PAPER DISPENSER: Height to Center of Roll (Max)	19"
PAPER TOWEL DISPENSER: Height to Operating Mechanism	48"
SHOWER: Top of Seat	17" - 19"
Grab Bar	33" - 36"
To Hand Shower Head Mounting (Max)	48"

This document is for interim review only.

ARCHITECT PBK Architects, Inc.

1801 Marlin Luther King Dr., San Antonio, TX 78203

ISSUE FOR CONSTRUCTION

ALAMO COLLEGES



CLIENT: Alamo Colleges
DATE: 2024/06/14
PROJECT NUMBER: 230462

ISSUE FOR CONSTRUCTION
BUILDING NUMBER: 1

TEAS ACCESSIBILITY STANDARDS




ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1808
ARCHITECTURE SOCIETY
AIA ARCHITECTS
LEED AP
LEED AP BD+C
LEED AP O+M
LEED AP S
LEED AP U
LEED AP V
LEED AP W
LEED AP W+BD
LEED AP W+BD+C
LEED AP W+BD+C+M+O
LEED AP W+BD+C+M+O+S
LEED AP W+BD+C+M+O+S+U
LEED AP W+BD+C+M+O+S+U+V
LEED AP W+BD+C+M+O+S+U+V+W
LEED AP W+BD+C+M+O+S+U+V+W+X
LEED AP W+BD+C+M+O+S+U+V+W+X+Y
LEED AP W+BD+C+M+O+S+U+V+W+X+Y+Z

1801 Marlin Luther King Dr., San Antonio, TX 78203
ISSUE FOR CONSTRUCTION

WFAC Black Box Addition PKG 1

ALAMO COLLEGES
ST. PHILIP'S COLLEGE



CLIENT: Alamo Colleges
DATE: 2024/06/14
PROJECT NUMBER: 230462

ISSUE FOR CONSTRUCTION
BUILDING NUMBER: 1

TEAS ACCESSIBILITY STANDARDS

Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.

ISSUE FOR PERMIT



CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
2101 BRUNNEN CELEBRITY LANDSCAPE DESIGN GROUP 113340000 LINDY & HARRIS ENGINEERING 113340000 T. J. JENSEN PROVIDER MEAN PROFESSIONALS 113340000 THEATRE 113340000	

WFAC Black Box Addition PKG 1

600 S. Milgram St.
San Antonio, TX 78203
ISSUE FOR PERMIT




CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
2024/06/12		
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT

BUILDING NUMBER

SITE PLAN

C200





LEGEND	
	PROPOSED ASPHALT PAVEMENT
	PROPOSED STRUCTURAL PAVEMENT

PARKING TABLE	
ITEM	QUANTITY
EXISTING PARKING SPOTS	125
EXISTING ADA SPOTS	9
REQUIRED ADA SPOTS	4
PROPOSED PARKING SPOTS	81
PROPOSED ADA SPOTS	8

IMPERVIOUS COVER COMPARISON			
	PERVIOUS	IMPERVIOUS	TOTAL
EXISTING	15497.11	66628.36	82125.47
PROPOSED	6426.58	75698.89	82125.47
IMPERVIOUS INCREASE		9070.53	

CHECKED BY:
SH & AL
DRAWN BY:
JC

ISSUE FOR CONSTRUCTION



LEGEND

[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT
[Symbol]	REF. STRUCTURAL
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. I PROP. STORM LINE
[Symbol]	EX. I PROP. WATER LINE
[Symbol]	EX. I PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. I PROP. GAS LINE
[Symbol]	EX. I PROP. DATA/TELECOM
[Symbol]	EX. I PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. I PROP. FIBER OPTIC
[Symbol]	EX. I PROP. OVERHEAD ELECTRIC
[Symbol]	EX. I PROP. FIRE HYDRANT
[Symbol]	EX. I PROP. WATER METER
[Symbol]	EX. I PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. I PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. I PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. I PROP. LIGHT POLE
[Symbol]	PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PROPOSED UTILITY EASEMENT

FIRE PROTECTION INFO

OWNER:	ST. PHILLIPS COLLEGE
SITE AREA (SF)	21,863
NO. OF STORIES	1
PROPOSED BUILDING	TOTAL GSF HEIGHT TYPE
	26,114 38 ft IIB
TOTAL REQUIRED FLOW (GPM)	3,500
BUILDING SPRINKLER SYSTEM:	YES
REDUCTION DUE TO SPRINKLERS:	75%
FINAL REQUIRED FIRE FLOW	875
AVAILABLE FLOW @ 20 PSI (GPM)	940






ARCHITECT: SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

ASSOCIATE ARCHITECT: SH & AL ARCHITECTS
1111 N. LOOP WEST
SUITE 1000
DALLAS, TEXAS 75201
214-760-1000
LINDY & HARRIS ENGINEERING
1111 N. LOOP WEST
SUITE 1000
DALLAS, TEXAS 75201
214-760-1000
MEASUREMENTS
1111 N. LOOP WEST
SUITE 1000
DALLAS, TEXAS 75201
214-760-1000

WFAC Black Box Addition PKG 1

600 S Miltman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT: Alamo Colleges

DATE: 2024/06/12 PROJECT NUMBER: 230462



No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER

SITE FIRE PLAN

ISSUE FOR CONSTRUCTION



LEGEND	
	PROPOSED ASPHALT PAVEMENT
	PROPOSED STRUCTURAL PAVEMENT REF. STRUCTURAL
	PROPOSED 4" CONCRETE SIDEWALK
	PROPOSED BUILDING
	EXISTING PAVEMENT EDGE
	PROPERTY LINE
	EXISTING EASEMENT
	PROPOSED EASEMENT
	EXISTING CONTOURS
	PROPOSED CONTOURS
	EX. PROP. STORM LINE
	EX. PROP. WATER LINE
	EX. PROP. SANITARY SEWER LINE
	EXISTING THERMALS
	PROPOSED THERMALS
	EX. PROP. GAS LINE
	EX. PROP. DATA/TELECOM
	EX. PROP. UNDERGROUND ELECTRIC
	EX. PROP. FIBER OPTIC
	EX. PROP. OVERHEAD ELECTRIC
	EX. PROP. FIRE HYDRANT EXPANSION JOINT
	EX. PROP. WATER METER CONTRACTION JOINT
	EX. PROP. GATE VALVE
	EX. IRRIGATION CONTROL VALVE
	PROP. FIRE DEPARTMENT CONNECTION
	PROP. POST INDICATOR VALVE
	PROP. HOSE LAY
	EX. PROP. SANITARY SEWER MANHOLE
	EX. PROP. SANITARY SEWER CLEANOUT
	EX. STORM SEWER MANHOLE
	PROP. STORM SEWER CURB INLET
	EX. PROP. LIGHT POLE
	PROPOSED PUBLIC ACCESS EASEMENT
	PROPOSED UTILITY EASEMENT






ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA & ARCHITECTS
DESIGNER	BA & ARCHITECTS
LANDSCAPE ARCHITECT	BA & ARCHITECTS
MECHANICAL ENGINEER	BA & ARCHITECTS
ELECTRICAL ENGINEER	BA & ARCHITECTS
CIVIL ENGINEER	BA & ARCHITECTS
PLUMBING ENGINEER	BA & ARCHITECTS
PROFESIONAL SEAL	BA & ARCHITECTS
REGISTERED PROFESSIONAL	BA & ARCHITECTS
REGISTERED	BA & ARCHITECTS
REGISTERED	BA & ARCHITECTS
REGISTERED	BA & ARCHITECTS

WFAC Black Box Addition PKG 1

600 S. Mittman St.
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
DRAWING HISTORY		
No.	Description	Date




ISSUE FOR CONSTRUCTION
BUILDING NUMBER

DIMENSION CONTROL & PAVING PLAN

C202

ISSUE FOR CONSTRUCTION

Sheet Grids Template
2400
FOR BLUEBAM LABELING.COR.





ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA & ARCHITECTS
DESIGNER	BA & ARCHITECTS
LANDSCAPE ARCHITECT	BA & ARCHITECTS
STRUCTURAL ENGINEER	LUNDY & HARRIS ENGINEERING
MECHANICAL ENGINEER	BA & ARCHITECTS
ELECTRICAL ENGINEER	BA & ARCHITECTS
PLUMBING ENGINEER	BA & ARCHITECTS
TELECOM ENGINEER	BA & ARCHITECTS
PROFESOR	BA & ARCHITECTS
REGISTERED PROFESSIONALS	BA & ARCHITECTS
REGISTERED	BA & ARCHITECTS
REGISTERED	BA & ARCHITECTS

WFAC Black Box Addition PKG 1

600 S Miltman St.
San Antonio, TX, 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER

EXISTING
CONDITIONS & DEMO
PLAN

C300

CHECKED BY:
SH & AL
DRAWN BY:
JC

ISSUE FOR CONSTRUCTION

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA & ARCHITECTS
1325 S. W. 13th St. San Antonio, TX 78204 210-492-2200 TX Firm BR 1608	
LANDSCAPE ARCHITECT	LANDSCAPE ARCHITECTS
1111 W. 15th St. San Antonio, TX 78204 210-492-2200 TX Firm BR 1608	
ENGINEER	LUNDY & HARRIS ENGINEERING
1111 W. 15th St. San Antonio, TX 78204 210-492-2200 TX Firm BR 1608	
PROFESSOR	MEAD
1111 W. 15th St. San Antonio, TX 78204 210-492-2200 TX Firm BR 1608	

LEGEND	
	EXISTING CONTOURS
	PROPOSED CONTOURS
	PROPERTY LINE
	PROPOSED SWALE WITH DIRECTION OF FLOW ARROWS
	GRADE BREAK
BR	PROPOSED FINISHED GRADE AT BOTTOM OF RAMP
BS	PROPOSED FINISHED GRADE AT BOTTOM OF STAIR
BW	PROPOSED FINISHED GRADE AT BASE OF WALL
FG	PROPOSED FINISHED GRADE ELEVATION
FL	PROPOSED FLOWLINE ELEVATION
G	PROPOSED GUTTER FLOWLINE ELEVATION
GB	PROPOSED GRADE BREAK
JB	PROPOSED TOP OF JUNCTION BOX ELEVATION
ME @ SW	MATCH EXISTING SIDEWALK ELEVATION
ME @ TC	MATCH EXISTING TOP OF CURB ELEVATION
ME @ TP	MATCH EXISTING TOP OF PAVEMENT ELEVATION
SW	PROPOSED TOP OF PAVEMENT AT SIDEWALK ELEVATION
TC	PROPOSED TOP OF CURB ELEVATION
TG	PROPOSED TOP OF GRATE ELEVATION
TP	PROPOSED TOP OF PAVEMENT ELEVATION
TR	PROPOSED TOP OF RAMP ELEVATION
TW	PROPOSED TOP OF WALL ELEVATION
TMS	PROPOSED TOP MUD SLAB
BMS	PROPOSED BOTTOM OF MUD SLAB

WFAC Black Box Addition PKG 1

KEY PLAN


CLIENT		Alamo Colleges
DATE	2024/06/12	PROJECT NUMBER
DRAWING HISTORY		230462
No.	Description	Date

ISSUE FOR CONSTRUCTION



BUILDING NUMBER

GRADING PLAN

C400



ISSUE FOR CONSTRUCTION



LEGEND



---	340	EXISTING CONTOURS
---	(340)	PROPOSED CONTOURS
---	---	PROPERTY LINE
---	---	PROPOSED SWALE WITH DIRECTION OF FLOW ARROWS
---	---	GRADE BREAK
BR		PROPOSED FINISHED GRADE AT BOTTOM OF RAMP
BS		PROPOSED FINISHED GRADE AT BOTTOM OF STAIR
BW		PROPOSED FINISHED GRADE AT BASE OF WALL
FG		PROPOSED FINISHED GRADE ELEVATION
FL		PROPOSED FLOWLINE ELEVATION
G		PROPOSED GUTTER FLOWLINE ELEVATION
GB		PROPOSED GRADE BREAK
JB		PROPOSED TOP OF JUNCTION BOX ELEVATION
ME @ SW		MATCH EXISTING SIDEWALK ELEVATION
ME @ TC		MATCH EXISTING TOP OF CURB ELEVATION
ME @ TP		MATCH EXISTING TOP OF PAVEMENT ELEVATION
SW		PROPOSED TOP OF PAVEMENT AT SIDEWALK ELEVATION
TC		PROPOSED TOP OF CURB ELEVATION
TG		PROPOSED TOP OF GRATE ELEVATION
TP		PROPOSED TOP OF PAVEMENT ELEVATION
TR		PROPOSED TOP OF RAMP ELEVATION
TW		PROPOSED TOP OF WALL ELEVATION
TMS		PROPOSED TOP MUD SLAB
BMS		PROPOSED BOTTOM OF MUD SLAB



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
2101 BRUNNEN LANDSCAPE 1131401002 LINDY & HARRIS ENGINEERING 1131401002 MEP NEAR PROFESSIONALS 1131401002 MEP 1208491860	

WFAC Black Box Addition PKG 1

600 S. Mittman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date



ISSUE FOR CONSTRUCTION

BUILDING NUMBER

CRAWLSPACE

C401

ISSUE FOR PERMIT



LEGEND




- DRAINAGE AREA BOUNDARY
- ⊙ A1 DRAINAGE AREA LABEL AND FLOW DIRECTION
- PROPERTY LINE
- EXISTING CONTOURS
- PROPOSED CONTOURS
- FLOW PATH

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1
600 S Milman St.
San Antonio, TX 78203
ISSUE FOR PERMIT



CLIENT Alamo Colleges
DATE 2024/06/12 PROJECT NUMBER 230462

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER
PRE DRAINAGE AREA MAP

C500

Pre AREA A					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	23001.03	0.53	0.50
Grass Cover	Grass Cover > 75%	0.35	5475.37	0.13	0.04
TOTAL			28476.40	0.65	0.55
			C		0.83

Pre AREA B					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	38420.17	0.88	0.84
Grass Cover	Grass Cover > 75%	0.35	6070.51	0.14	0.05
TOTAL			44490.68	1.02	0.89
			C		0.87

Pre AREA C					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	5207.16	0.12	0.11
Grass Cover	Grass Cover > 75%	0.35	3951.23	0.09	0.03
TOTAL			9158.39	0.21	0.15
			C		0.70

PRE DEVELOPMENT PEAK RUNOFF

AREA	SIZE (AC)	C	TC (MIN)	1 YR (CFS)	5 YR (CFS)	25 YR (CFS)	100 YR (CFS)
A	0.65	0.83	5.0	2.9	4.2	5.9	7.4
B	1.02	0.87	5.0	4.7	7.0	9.7	12.2
C	0.21	0.70	9.0	0.7	1.0	1.3	1.6



Atlas 14 Rainfall Intensity (in/hr)

Time (minutes)	1 - YEAR	5 - YEAR	25 - YEAR	100 - YEAR
5	5.29	7.88	11.00	13.79
6	5.07	7.45	10.43	13.08
7	4.86	7.11	9.95	12.49
8	4.64	6.81	9.54	11.97
9	4.43	6.54	9.17	11.49
10	4.21	6.30	8.82	11.05

Pre			
Area A	0.83	Area B	0.87
C	0.65	C	1.02
Area (ac)	0.65	Area (ac)	1.02
Flow Length (ft)	315.12	Flow Length (ft)	479.97
SCS Sheet Flow (ft)	68.20	SCS Sheet Flow (ft)	85.32
Slope (%)	1.02	Slope (%)	1.28
Manning's Roughness	0.013	Manning's Roughness	0.013
Flow Time (min)	1.06	Flow Time (min)	1.16
SCS Shallow Concentrated Flow (ft)	246.92	SCS Shallow Concentrated Flow (ft)	180.17
PAVEMENT		PAVEMENT	
Slope (%)	1.00	Slope (%)	0.86
Velocity (ft/s)	2.03	Velocity (ft/s)	1.89
Flow Time (min)	2.03	Flow Time (min)	1.59
Time of Concentration (min)	3.09	SCS Channel Flow (ft)	153.60
<i>*COSA requires min TOC of 5 min*</i>			
		Slope (%)	0.21
		Manning's Roughness	0.012
		Velocity (ft/s)	2.95
		Flow Time (min)	0.85
		SCS Channel Flow (ft)	60.88
		Slope (%)	1.79
		Manning's Roughness	0.011
		Velocity (ft/s)	6.50
		Flow Time (min)	0.10
		Time of Concentration (min)	3.70
<i>*COSA requires min TOC of 5 min*</i>			

ISSUE FOR PERMIT

Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.



LEGEND

- DRAINAGE AREA BOUNDARY
- (A1) DRAINAGE AREA LABEL AND FLOW DIRECTION
- PROPERTY LINE
- - - - - EXISTING CONTOURS
- - - - - PROPOSED CONTOURS
- FLOW PATH



Required Storage	
Storm Event	Required Storage (ft ³)
1 - Year	2037.00
5 - Year	2784.00
25 - Year	3698.00
100 - Year	4549.00



ARCHITECT: SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1

600 S Milburn St.
San Antonio, TX 78203
ISSUE FOR PERMIT



No.	Description	Date
1	ADDENDUM 1	08/05/2024

CLIENT: Alamo Colleges
DATE: 2024/06/12 PROJECT NUMBER: 230462

ISSUE FOR PERMIT
BUILDING NUMBER

POST DRAINAGE AREA MAP
C501

POST AREA A					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	2700.94	0.06	0.06
Grass Cover	Grass Cover > 75%	0.35	54.6	0.00	0.00
TOTAL			2755.54	0.06	0.06
			C 0.94		

POST AREA B					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	67228.61	1.54	1.47
Grass Cover	Grass Cover > 75%	0.35	4672.06	0.11	0.04
TOTAL			71900.67	1.65	1.50
			C 0.91		

POST AREA C					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	5769.34	0.13	0.13
Grass Cover	Grass Cover > 75%	0.35	1699.92	0.04	0.01
TOTAL			7469.26	0.17	0.14
			C 0.81		



POST DEVELOPMENT PEAK RUNOFF							
AREA	SIZE (AC)	C	TC (MIN)	1 YR (CFS)	5 YR (CFS)	25 YR (CFS)	100 YR (CFS)
A	0.06	0.94	5.0	0.3	0.4	0.6	0.8
B	1.65	0.91	5.0	8.2	12.2	16.9	21.2
C	0.17	0.81	8.0	0.6	0.9	1.3	1.6

Time (minutes)	Atlas 14 Rainfall Intensity (in/hr)			
	1 - YEAR	5 - YEAR	25 - YEAR	100 - YEAR
5	5.29	7.88	11.00	13.79
6	5.07	7.45	10.43	13.08
7	4.86	7.11	9.95	12.49
8	4.64	6.81	9.54	11.97
9	4.43	6.54	9.17	11.49
10	4.21	6.30	8.82	11.05

Post			
Area A	Area B	Area C	
C	0.94	C	0.81
Area (ac)	0.06	Area (ac)	0.17
Flow Length (ft)	29.10	Flow Length (ft)	70.70
SCS Sheet Flow (ft)	29.10	SCS Sheet Flow (ft)	24.73
Slope (%)	0.99	Slope (%)	0.83
Manning's Roughness	0.011	Manning's Roughness	0.300
Flow Time (min)	0.54	Flow Time (min)	7.18
Time of Concentration (min)	0.54	SCS Shallow Concentrated Flow (ft)	81.23
COSA requires min TOC of 5 min			
PAVEMENT			
Slope (%)	0.65	Manning's Roughness	0.011
Velocity (ft/s)	1.64	Flow Time (min)	0.40
Flow Time (min)	0.83	Time of Concentration (min)	8.00
COSA requires min TOC of 5 min			
SCS Channel Flow (ft)	224.55		
Slope (%)	0.50		
Manning's Roughness	0.011		
Velocity (ft/s)	5.00		
Flow Time (min)	0.74		
SCS Channel Flow (ft)	25.67		
Slope (%)	0.50		
Manning's Roughness	0.011		
Velocity (ft/s)	7.00		
Flow Time (min)	0.06		
Time of Concentration (min)	2.95		
COSA requires min TOC of 5 min			

Sheet Grids Template
 Z400
 FOR BLUEBAM LABELING.COR.

ISSUE FOR PERMIT





LEGEND

[Pattern]	PROPOSED ASPHALT PAVEMENT
[Pattern]	PROPOSED STRUCTURAL PAVEMENT
[Pattern]	REF. STRUCTURAL
[Pattern]	PROPOSED 4" CONCRETE SIDEWALK
[Pattern]	PROPOSED BUILDING
[Line]	EXISTING PAVEMENT EDGE
[Line]	PROPERTY LINE
[Line]	EXISTING EASEMENT
[Line]	PROPOSED EASEMENT
[Line]	EXISTING CONTOURS
[Line]	PROPOSED CONTOURS
[Line]	EX. PROP. STORM LINE
[Line]	EX. PROP. WATER LINE
[Line]	EX. PROP. SANITARY SEWER LINE
[Line]	EXISTING THERMALS
[Line]	PROPOSED THERMALS
[Line]	EX. PROP. GAS LINE
[Line]	EX. PROP. DATA/TELECOM
[Line]	EX. PROP. UNDERGROUND ELECTRIC
[Line]	EX. PROP. FIBER OPTIC
[Line]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PROPOSED UTILITY EASEMENT



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
2101 BRASS LANDSCAPE 1131 W. 15TH LUNY & HARRIS ENGINEERING 1131 W. 15TH PROLOGUE NEAR PROLOGUE 1131 W. 15TH 1131 W. 15TH	

WFAC Black Box Addition PKG 1



CLIENT	Alamo Colleges
DATE	2024/06/12
PROJECT NUMBER	230462

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT

BUILDING NUMBER

OVERALL UTILITY

C600

CHECKED BY:
 SH & AL
 DRAWN BY:
 JC


ISSUE FOR CONSTRUCTION



ARCHITECT: SAN ANTONIO, TX
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1608

WFAC Black Box Addition PKG 1

ALAMO COLLEGES
 ST. PHILIP'S COLLEGE




STATE OF TEXAS
 ANDREW A. LANGE
 118770
 06/14/2024

CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date



ISSUE FOR CONSTRUCTION
 BUILDING NUMBER

ELEC. & COMMS PLAN & PROFILES


C700



NOTE: CONTRACTOR TO FIELD VERIFY EXISTING UTILITY INVERTS PRIOR TO CONSTRUCTION



EL-02
 SCALE: 1"=20' H, 1"=5' V




FO-01
 SCALE: 1"=20' H, 1"=5' V

LEGEND	
[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT REF. STRUCTURAL
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. PROP. STORM LINE
[Symbol]	EX. PROP. WATER LINE
[Symbol]	EX. PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. PROP. GAS LINE
[Symbol]	EX. PROP. DATA/TELECOM
[Symbol]	EX. PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. PROP. FIBER OPTIC
[Symbol]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PROPOSED UTILITY EASEMENT




Sheet Grids Template
Z:400
FOR BLUEBAM LABELING CORR.

ISSUE FOR PERMIT



ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400	San Antonio, TX 78216
210-829-0123 P	210-829-0578 F
TX Firm BR 1608	
PROJECT ARCHITECT	PBK ARCHITECTS
DESIGNER	PBK ARCHITECTS
LANDSCAPE ARCHITECT	PBK ARCHITECTS
ENGINEER	PBK ARCHITECTS
TRUCKER	PBK ARCHITECTS
LANDSCAPE ARCHITECT	PBK ARCHITECTS
ENGINEER	PBK ARCHITECTS
TRUCKER	PBK ARCHITECTS
PROJECT ARCHITECT	PBK ARCHITECTS
DESIGNER	PBK ARCHITECTS
LANDSCAPE ARCHITECT	PBK ARCHITECTS
ENGINEER	PBK ARCHITECTS
TRUCKER	PBK ARCHITECTS

WFAC Black Box Addition PKG 1




CLIENT	Alamo Colleges
DATE	2024/06/12
PROJECT NUMBER	230462

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

STORM PLAN


C800



LEGEND


[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. PROP. STORM LINE
[Symbol]	EX. PROP. WATER LINE
[Symbol]	EX. PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. PROP. GAS LINE
[Symbol]	EX. PROP. DATA/TELECOM
[Symbol]	EX. PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. PROP. FIBER OPTIC
[Symbol]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PROPOSED UTILITY EASEMENT

CHECKED BY: SH & AL
DRAWN BY: JC




ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608
PROFESOR	ANDREW A. LANGE 118770 11/15/2024
REGISTERED ARCHITECT	ANDREW A. LANGE 118770 11/15/2024
REGISTERED LANDSCAPE ARCHITECT	ANDREW A. LANGE 118770 11/15/2024
REGISTERED ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED SURVEYOR	ANDREW A. LANGE 118770 11/15/2024
REGISTERED PLUMBER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED ELECTRICIAN	ANDREW A. LANGE 118770 11/15/2024
REGISTERED MECHANICAL ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED CIVIL ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED CHEMICAL ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED METALLURGY ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED INDUSTRIAL ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED AEROSPACE ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED NUCLEAR ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED TRANSPORTATION ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED ENVIRONMENTAL ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED SAFETY ENGINEER	ANDREW A. LANGE 118770 11/15/2024
REGISTERED PROFESSIONAL ENGINEER	ANDREW A. LANGE 118770 11/15/2024


NOTE: CONTRACTOR TO FIELD VERIFY EXISTING UTILITY INVERTS PRIOR TO CONSTRUCTION




ST-1
SCALE: 1"=20' H, 1"=5' V




ST-2
SCALE: 1"=20' H, 1"=5' V




ST-3
SCALE: 1"=20' H, 1"=5' V



ST-5
SCALE: 1"=20' H, 1"=5' V





ST-4
SCALE: 1"=20' H, 1"=5' V



ST-6
SCALE: 1"=20' H, 1"=5' V

WFAC Black Box Addition PKG 1



CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

STORM PROFILES

ISSUE FOR PERMIT

ISSUE FOR PERMIT

Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.




CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
2101 BRUNNEN CELEBRITY LANDSCAPE DESIGN GROUP 1133400000 1133400000 LUNDY & HARRIS ENGINEERING 1133400000 1133400000 1133400000 1133400000 1133400000 1133400000 1133400000 1133400000	

WFAC Black Box Addition PKG 1

600 S Miltman St.
San Antonio, TX 78203
ISSUE FOR PERMIT





CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

DETENTION PLAN

C802



UNDERGROUND DETENTION OUTLET STRUCTURE
N.T.S.
NOTES:
1. ALL REINFORCEMENT BARS TO HAVE 2\"/>

CHECKED BY: SH & AL
DRAWN BY: JC

ISSUE FOR CONSTRUCTION





ARCHITECT SAN ANTONIO **PBK Architects, Inc.**
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1

600 S Miltman St.
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



STATE OF TEXAS
ANDREW A. LANGE
118770
06/14/2024

No.	Description	Date


CLIENT Alamo Colleges
DATE 2024/06/12 PROJECT NUMBER 230462

ISSUE FOR CONSTRUCTION

BUILDING NUMBER



SANITARY PLAN & PROFILES

C900





NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING UTILITY INVERTS PRIOR TO CONSTRUCTION

LEGEND	
	PROPOSED ASPHALT PAVEMENT
	PROPOSED STRUCTURAL PAVEMENT
	PROPOSED 4\"/>
	PROPOSED BUILDING
	EXISTING PAVEMENT EDGE
	PROPERTY LINE
	EXISTING EASEMENT
	PROPOSED EASEMENT
	EXISTING CONTOURS
	PROPOSED CONTOURS
	EX. PROP. STORM LINE
	EX. PROP. WATER LINE
	EX. PROP. SANITARY SEWER LINE
	EXISTING THERMALS
	PROPOSED THERMALS
	EX. PROP. GAS LINE
	EX. PROP. DATA/TELECOM
	EX. PROP. UNDERGROUND ELECTRIC
	EX. PROP. FIBER OPTIC
	EX. PROP. OVERHEAD ELECTRIC
	EX. PROP. FIRE HYDRANT
	EX. PROP. WATER METER
	EX. PROP. GATE VALVE
	EX. IRRIGATION CONTROL VALVE
	PROP. FIRE DEPARTMENT CONNECTION
	PROP. POST INDICATOR VALVE
	PROP. HOSE LAY
	EX. PROP. SANITARY SEWER MANHOLE
	EX. PROP. SANITARY SEWER CLEANOUT
	EX. STORM SEWER MANHOLE
	PROP. STORM SEWER CURB INLET
	EX. PROP. LIGHT POLE
	PROPOSED PUBLIC ACCESS EASEMENT
	PROPOSED UTILITY EASEMENT




SA-1
SCALE: 1"=20' H, 1"=5' V


ISSUE FOR CONSTRUCTION
 Sheet Grids Template
 FOR BLUEBIRD LABELING COOR.



NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING UTILITY INVERTS PRIOR TO CONSTRUCTION



WA-1
SCALE: 1"=20' H, 1"=5' V



WA-2
SCALE: 1"=20' H, 1"=5' V



LEGEND

[Pattern]	PROPOSED ASPHALT PAVEMENT
[Pattern]	PROPOSED STRUCTURAL PAVEMENT
[Pattern]	REF. STRUCTURAL
[Pattern]	PROPOSED 4\"/>



ARCHITECT SAN ANTONIO **PBK Architects, Inc.**
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1608

WFAC Black Box Addition PKG 1
 600 S Mittman St.
 San Antonio, TX 78203
 ISSUE FOR CONSTRUCTION



CLIENT: Alamo Colleges
 DATE: 2024/06/12 PROJECT NUMBER: 230462
 DRAWING HISTORY



No.	Description	Date

ISSUE FOR CONSTRUCTION
 BUILDING NUMBER
WATER PLAN & PROFILES

C1000

CHECKED BY: SH & AL
 DRAWN BY: JC

ISSUE FOR CONSTRUCTION



LEGEND

	CONSTRUCTION ENTRANCE, INSTALLED PER DETAIL
	PROPERTY LINE
	EXISTING CONTOURS
	PROPOSED CONTOURS
	EXISTING FLOW PATH
	PROPOSED FLOW PATH
	SILT FENCE, INSTALLED PER DETAIL
	PROPOSED DAM EROSION CONTROL, LOG-18"
	PROPOSED ROCK FILTER DAM TYPE 3
	PROP. TREE PROTECTION FENCE
	PROP. TREE PROTECTION FENCE

EROSION CONTROL NOTES:
OWNER INFORMATION: ST PHILLIPS COLLEGE
PROJECT NAME: ST PHILLIPS COLLEGE WATSON FINE ARTS CENTER BLACK BOX ADDITION
PROJECT LOCATION: 600 S MITTMAN ST. SAN ANTONIO, TX 78203

LATITUDE: 29°24'49.57"N
LONGITUDE: 98°27'14.61"W
TOTAL SITE AREA IS: 1.89 ACRES
TOTAL AREA OF SITE EXPECTED TO BE DISTURBED: 1.35 ACRES

EXISTING SITE CONDITIONS
LAND USE: HIGHER EDUCATION
LAND COVER: ~90% IMPERVIOUS
RECEIVING WATERS: SALADO CREEK
SEGMENT NO. OF CLASSIFIED WATER BODY: SALADO CREEK
BASIN NAME: SAN ANTONIO RIVER

SOIL INFORMATION
HYDROLOGIC SOIL GROUP: D

POST DEVELOPED SITE CONDITIONS
LAND USE: HIGHER EDUCATION
ACADEMIC BLDG

NATURE OF ACTIVITIES
ACADEMIC BLDG

- SEQUENCE OF MAJOR ACTIVITIES**
1. INSTALL SILT FENCE AT STOCK PILE AREAS
 2. CLEARING, GRADING, GENERAL CONSTRUCTION SITE
 3. INSTALL FILTER ELEMENTS IMMEDIATELY AFTER DISTURBANCE AND/OR GRADING OPERATIONS.
 4. AFTER ESTABLISHMENT OF GRASS, REMOVE ALL TEMPORARY EROSION CONTROL.
 5. SEED ALL AREAS NOT HAVING PERMANENT GRASS COVERAGE AFTER APPROVAL BY COUNTY INSPECTOR.

- GENERAL EROSION CONTROL NOTES**
1. ALL UTILITIES AND SERVICE LINES SHOWN ARE TAKEN FROM RECORD INFORMATION SUPPLIED BY THE UTILITY OWNER OR HORIZONTALLY LOCATED BY INDEPENDENT LOCATORS. CONTRACTOR IS RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN PLAN AND ACTUAL CONDITIONS PRIOR TO CONSTRUCTION. OWNER AND ENGINEER SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF INFORMATION OR DATA RELIED ON TO DEPICT UNDERGROUND FACILITIES. CONTRACTOR IS TO CONTACT OWNERS OF ALL UTILITIES AND SERVICE LINES WITHIN THE PROJECT AREA AND NOTIFY OF INTENT AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH FACILITY OWNERS, CONTRACTOR IS TO VERIFY THE EXACT LOCATION AND VERTICAL POSITIONING OF ALL PIPELINES, EXISTING UTILITIES, AND SERVICE LINES WITHIN THE PROJECT AREA WHETHER SHOWN ON THE PLANS OR NOT, AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. CONTRACTOR IS TO MAINTAIN STRUCTURAL INTEGRITY OF ALL PIPELINES, ELECTRIC TRANSMISSION POLES AND LINES, PERMANENT AND TEMPORARY UTILITIES. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE DONE TO EXISTING UTILITY FACILITIES, PAVEMENT, ETC. AS A RESULT OF CLEARING/DIRTWORK ACTIVITIES.
 2. CONTRACTOR TO CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.
 3. ALL DISTURBED AREAS NOT TO BE PAVED ARE TO HAVE ESTABLISHMENT OF GRASS.
 4. ALL SWALE AREAS (BOTTOM WIDTHS & SIDE SLOPES) ARE TO BE PREPARED AND HYDROMULCHED FOR PERMANENT ESTABLISHMENT OF VEGETATION. PRIOR TO HYDROMULCHING OPERATIONS, CONTRACTOR TO REPLACE TOPSOIL TO A DEPTH OF 6". TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND LIGHTLY COMPACTED. FINAL GRADES WITH ESTABLISHED VEGETATION SHALL BE AS CALLED OUT ON THE GRADING PLAN.
 5. CONTRACTOR IS TO MAINTAIN EROSION CONTROL AT ALL LOCATIONS OF CONSTRUCTION THROUGHOUT DURATION OF THE PROJECT AND UNTIL VEGETATION IS ESTABLISHED. INSURE SEDIMENT IS NOT TRANSPORTED DOWNSTREAM FROM PROJECT VIA GRAVEL FILTER BAGS AND SILT FENCE INSTALLATIONS. IF EXCESSIVE EROSION IS OBSERVED IN THE FIELD, ADDITIONAL EROSION CONTROLS SHALL BE INSTALLED.
 6. CONTRACTOR SHALL NOT ALLOW SEDIMENT TO ENTER THE DOWNSTREAM CHANNEL. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING OF THE DOWNSTREAM CHANNEL AREAS AND RESTORING TO ORIGINAL CONDITION, INCLUDING ESTABLISHMENT OF REVEGETATION SHOULD CONSTRUCTION SEDIMENT BE FOUND OUTSIDE THE LIMITS OF CONSTRUCTION.
 7. THE CONTRACTOR WILL REMOVE ALL EXCESS SOIL FROM CONSTRUCTION VEHICLES PRIOR TO EXITING THE SITE.
 8. THE CONTRACTOR SHALL UNDERTAKE PROPER METHODS TO REDUCE DUST GENERATION FROM THE SITE.
 9. THE CONTRACTOR MUST COMPLY WITH FEDERAL, STATE, AND LOCAL REGULATIONS REGARDING SEDIMENTS AND EROSION CONTROL.
 10. A COPY OF THIS PLAN MUST BE KEPT AT THE CONSTRUCTION FACILITY DURING THE ENTIRE CONSTRUCTION PERIOD.
 11. ALL FINISHED GRADES ARE TO BE HYDRO-MULCHED, SPOT SODDED OR SEEDED AND WATERED UNTIL GROWTH IS ESTABLISHED.
 12. CONTRACTOR IS RESPONSIBLE TO FILE THE NOTICE OF INTENT AND NOTICE OF TERMINATION WITH AUTHORITY HAVING JURISDICTION.






ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA ARCHITECTS
1711 W. Loop West Suite 200 San Antonio, TX 78201 210-441-0992	
LANDSCAPE ARCHITECT	LUNY & HARRIS ENGINEERING
1711 W. Loop West Suite 200 San Antonio, TX 78201 210-441-0992	
PROVIDER	MEAN PROFESSIONALS
1711 W. Loop West Suite 200 San Antonio, TX 78201 210-441-0992	

WFAC Black Box Addition PKG 1

600 S Miltman St.
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION


BUILDING NUMBER

EROSION CONTROL


C1100

GENERAL NOTES

1. NEW PIPE TO BE SET FLUSH WITH INSIDE WALL OF STRUCTURE.




GRAouted STORM SEWER CONNECTION DETAIL
NTS




PROPOSED MANHOLE ON EXISTING BOX STORM SEWER
NTS

TABLE
SEWER SIZE VS. OPENING

SEWER SIZE (INCHES)	MANHOLE BASE DIAMETER
48"	36"
54"	36"
60"	42"
66" OR GREATER	48"




INTEGRAL CURB & GUTTER
NTS




NOTE: SEE PLAN C.X.X FOR JOINT LOCATIONS

CONCRETE TO ASPHALT J-JOINT
NTS




1 1/2" HMAC PAVEMENT
NTS




NOTE: SIDEWALK EXPANSION JOINTS SHALL BE INSTALLED AS SHOWN ON PLANS

SIDEWALK EXPANSION JOINT
NTS




NOTE: SIDEWALK JOINT SPACING PER LANDSCAPE ARCHITECT OR JOINT PLAN. IF NOT SPECIFIED, SPACING SHALL BE EQUAL TO SIDEWALK WIDTH WITH A MAXIMUM SPACING OF 8-FOOT.

SIDEWALK CONTRACTION JOINT
NTS




NOTES:
1. SUBGRADE STABILIZATION SHALL BE PER GEOTECHNICAL RECOMMENDATIONS AND LIME/CEMENT SERIES BASED ON ACTUAL SUBGRADE CONDITIONS.
2. SAW CUT OPERATIONS SHALL BEGIN AS SOON AS POSSIBLE AFTER CONCRETE PLACEMENT.
3. SEAL ALL EXPANSION JOINTS WITH SEAL CAP AND CONTROL JOINTS WITH SELF LEVELING JOINT SEALANT MATERIAL PER SPECIFICATIONS. USE SELF LEVELING JOINT SEALANT ADJACENT TO EXISTING PAVEMENT.

SIDEWALK SECTION
NTS




NOTES:
1. SEE PLAN FOR JOINT SPACING, COMPRESSIVE STRENGTH, PAVEMENT THICKNESS, AND REINFORCING.
2. DEPTH OF STABILIZATION SHALL BE A MINIMUM OF 6 INCHES OR BASED ON GEOTECHNICAL RECOMMENDATIONS SUBGRADE CONDITIONS.
3. SUBGRADE STABILIZATION SHALL BE PER GEOTECHNICAL RECOMMENDATIONS AND LIME/CEMENT SERIES BASED ON ACTUAL SUBGRADE CONDITIONS.

CONCRETE PAVEMENT
NTS




NOTES:
1. SEE PLANS FOR JOINT SPACING, COMPRESSIVE STRENGTH, PAVEMENT THICKNESS, AND REINFORCING.
2. SAW CUT OPERATIONS SHALL BEGIN AS SOON AS POSSIBLE AFTER CONCRETE PLACEMENT.
3. SEAL ALL JOINTS WITH SELF LEVELING JOINT SEALANT MATERIAL PER SPECIFICATIONS.

CONTROL JOINT
NTS



EXPANSION JOINT
NTS




A. SATISFACTORY SOILS
MATERIAL EXCAVATED FROM THE DITCH, (WHICH IS FREE OF ROCKS, LUMPS, CLODS, OR DEBRIS LARGER THAN TWO (2) INCHES IN THE LARGEST DIMENSION), COMPACTED TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NON-STRUCTURAL AREAS (IE. YARDS, PASTURES, EASEMENTS) AND TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NEW STREET AND PAVEMENT AREAS.

B. BANK RUN SAND
GRANULAR MATERIAL FREE OF DETRIMENTAL QUANTITIES OF CLAY, DEBRIS, OR ORGANIC MATERIAL. REFERENCE SPECIFICATION FOR REQUIREMENTS.

C. CEMENT STABILIZED SAND
MATERIALS SHALL BE TYPE PORTLAND CEMENT CONFORMING TO ASTM C150 AND CLEAN DURABLE SAND MEETING GRADING REQUIREMENTS FOR FINE AGGREGATES OF ASTM C33. THE CEMENT STABILIZED SAND SHALL HAVE A MINIMUM OF 10% CEMENT PER CUBIC YARD OF CEMENT STABILIZED SAND MIXTURE, BASED ON LOOSE DRY WEIGHT VOLUME (AT LEAST 2.5 SACKS OF CEMENT PER CUBIC YARD OF MIXTURE). COMPACT MIX TO 90% OF ASTM D698 WITH A MOISTURE CONTENT BETWEEN .2% TO 2% ABOVE OPTIMUM.

D. PAVEMENT SUBGRADE
REFERENCE PAVEMENT SECTION DETAIL AND SPECIFICATION FOR MATERIALS AND DEPTHS.




A. SATISFACTORY SOILS
MATERIAL EXCAVATED FROM THE DITCH, (WHICH IS FREE OF ROCKS, LUMPS, CLODS, OR DEBRIS LARGER THAN TWO (2) INCHES IN THE LARGEST DIMENSION), COMPACTED TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NON-STRUCTURAL AREAS (IE. YARDS, PASTURES, EASEMENTS) AND TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NEW STREET AND PAVEMENT AREAS.

B. BANK RUN SAND
GRANULAR MATERIAL FREE OF DETRIMENTAL QUANTITIES OF CLAY, DEBRIS, OR ORGANIC MATERIAL. REFERENCE SPECIFICATION FOR REQUIREMENTS.

C. CEMENT STABILIZED SAND
MATERIALS SHALL BE TYPE PORTLAND CEMENT CONFORMING TO ASTM C150 AND CLEAN DURABLE SAND MEETING GRADING REQUIREMENTS FOR FINE AGGREGATES OF ASTM C33. THE CEMENT STABILIZED SAND SHALL HAVE A MINIMUM OF 10% CEMENT PER CUBIC YARD OF CEMENT STABILIZED SAND MIXTURE, BASED ON LOOSE DRY WEIGHT VOLUME (AT LEAST 2.5 SACKS OF CEMENT PER CUBIC YARD OF MIXTURE). COMPACT MIX TO 90% OF ASTM D698 WITH A MOISTURE CONTENT BETWEEN .2% TO 2% ABOVE OPTIMUM.

D. PAVEMENT SUBGRADE
REFERENCE PAVEMENT SECTION DETAIL AND SPECIFICATION FOR MATERIALS AND DEPTHS.





GENERAL NOTES:
ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOCK SOODED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOCK SOO WILL BE REQUIRED. BARED AREAS SHALL BE SEEDED OR SOODED WITHIN 14 CALENDAR DAYS OF LAST DISTURBANCE.

APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.

ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.



ESTABLISHMENT OF VEGETATION MAY BE A WARRANTY ITEM.

BEDDING AND TRENCH FOR HDPE PIPE
NTS





SINGLE GRATE INLET
NTS

STORM SEWER JUNCTION BOX
NTS



REQUIREMENTS- BERMS MAY BE REQUIRED





GRATE INLET
NTS



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1



CLIENT	Alamo Colleges
DATE	2024/06/12
PROJECT NUMBER	230462

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER


DETAILS

C1200


ISSUE FOR PERMIT

GENERAL NOTES:

- FINELY DIVIDED EARTH FREE OF ROCK, LUMPS AND CLODS EXCEEDING 6" SHALL BE PLACED BY HAND, AND COMPACTED AROUND THE CAST IRON PIPE TO A DEPTH OF 12" OVER THE TOP OF THE PIPE BEFORE BACKFILL IS BEGUN BY ANY MECHANICAL EQUIPMENT.
- ALL CONCRETE BLOCKING SHALL BE - 28 DAY CONCRETE STRENGTH = 2000psi.
- ALL THRUST BLOCKING SHALL PROVIDE A MINIMUM OF 2 SQUARE FEET OF BEARING AREA OF CONCRETE ON UNDISTURBED SOIL, OR AS DIRECTED BY THE ENGINEER.
- WATER MAINS WILL NOT BE FULLY PRESSURIZED UNTIL CONCRETE HAS REACHED 7 DAY STRENGTH.
- ALL PIPE WILL BE LAID SO AS THE ENTIRE BARRELL WILL HAVE FULL BEARING ON THE FINE GRADED TRENCH BOTTOM. BELL HOLES SHALL BE CUT FOR EACH BELL AND FIRE HYDRANT.
- ALL FITTINGS SHALL BE MECHANICAL JOINTS UNLESS OTHERWISE DIRECTED.
- HYDRANTS SHALL BE LOCATED NO CLOSER THAN 3 FEET MEASURED FROM THE BACK OF CURB TO THE FACE OF THE STEAMER ON THE FIRE HYDRANT.




STANDARD FIRE HYDRANT ASSEMBLY
NTS




- SATISFACTORY SOILS**
MATERIAL EXCAVATED FROM THE DITCH, (WHICH IS FREE OF ROCKS, LUMPS, CLODS, OR DEBRIS LARGER THAN TWO (2) INCHES IN THE LARGEST DIMENSION), COMPACTED TO A MINIMUM OF 95% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN -2% TO 2% ABOVE OPTIMUM UNDER NON-STRUCTURAL AREAS (I.E., YARDS, PASTURES, EASEMENTS) AND TO A MINIMUM OF 98% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN -2% TO 2% ABOVE OPTIMUM UNDER PAVED AREAS.
- CEMENT STABILIZED SAND**
MATERIALS SHALL BE TYPE I PORTLAND CEMENT CONFORMING TO ASTM C150 AND CLEAN DURABLE SAND MEETING GRADING REQUIREMENTS FOR FINE AGGREGATES OF ASTM C33. THE CEMENT STABILIZED SAND SHALL HAVE A MINIMUM OF 10% CEMENT PER CUBIC YARD OF CEMENT STABILIZED SAND MIXTURE, BASED ON LOOSE DRY WEIGHT VOLUME (AT LEAST 2 SACKS OF CEMENT PER CUBIC YARD OF MIXTURE), COMPACT MIX TO 95% OF ASTM D558 WITH A MOISTURE CONTENT BETWEEN -2% TO 2% ABOVE OPTIMUM.
- PAVEMENT SUBGRADE**
REFERENCE PAVEMENT SECTION DETAIL AND SPECIFICATION FOR MATERIALS AND DEPTHS.

GENERAL NOTES:
 ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOC SODDED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOC SOD WILL BE REQUIRED. BARED AREAS SHALL BE SEED OR SODDED WITHIN 14 CALENDAR DAYS OF LAST DISTURBANCE.
 APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.
 ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.
 ESTABLISHMENT OF VEGETATION MAY BE A WARRANTY ITEM


BEDDING AND TRENCH FOR REINFORCED CONCRETE PIPE
NTS



FIRE HYDRANT LOCATION REALIGN AS NEEDED




VIEW A-A




PVC EMBEDMENT TRENCH


- NOTES:**
- GRANULAR BACKFILL SHALL MEET THE SPECIFICATIONS OF TXDOT TYPE A.
 - ONSITE MATERIAL FOR FILL SHALL BE FREE OF DEBRIS AND GRAVEL LARGER THAN 2" IN DIAMETER.
 - UNDER PAVED AREAS, ONSITE FILL SHALL BE STABILIZED AS REQUIRED BY THE GEOTECHNICAL ENGINEER. BACKFILL SHALL BE COMPACTED TO 98% STANDARD PROCTOR DENSITY.
 - UNDER NON-PAVED AREAS, ONSITE FILL MAY BE USED AND SHALL BE COMPACTED IN 10" LIFTS TO 90% STANDARD PROCTOR DENSITY.




SILT CONTROL FENCE
NTS




CONSTRUCTION ENTRANCE/EXIT
NTS




OPENING CREATION DETAIL




MANHOLE CONNECTION DETAIL



STANDARD MANHOLE TIE-IN
NTS








PLAN




SECTION A-A

PROPERTY OF SAN ANTONIO WATER SYSTEM SAN ANTONIO, TEXAS	APPROVED March 2008	REVISED AUG 2019	DD-824-09
6" TURBINE METER INSTALLATION		SHEET 2 OF 2	




STORM DRAIN INLET PROTECTION
NTS

NOTE:
 TEMPORARY DEVICES AROUND STORM DRAINS ARE USED TO DETAIN AND/OR FILTER SEDIMENT-LADEN RUNOFF. THE PROTECTION ALLOWS SEDIMENT TO SETTLE PRIOR TO DISCHARGE INTO A STORM DRAIN INLET OR CATCH BASIN. SAND BAGS SHALL BE UV RESISTANT AND MUST NOT DEGRADE DUE TO ATMOSPHERIC CONDITIONS. SAND BAGS SHALL BE REPLACED UPON FIRST SIGN OF DETRIORATION.



SECTION B-B

- NOTE:**
- 1" DIA. "STARTER HOLES SHALL BE DRILLED THROUGH WALL OF EXISTING MANHOLE SPACED 3" APART CENTER TO CENTER. AFTER "STARTER" HOLES HAVE BEEN INSTALLED AND APPROVED BY A CITY INSPECTOR, THE CONTRACTOR SHALL BEGIN REMOVING THE CONCRETE INSIDE THE PERIPHERAL "STARTER" HOLES. CONCRETE SHALL BE REMOVED WITH PNEUMATIC HAND TOOLS.
 - THE NUMBER OF REBAR DOWELS SHALL VARY WITH SIZE OF OPENING. REBAR SHALL NOT BE SPACED MORE THAN 12" OC.
 - WATERSTOP SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURERS REQUIREMENTS.
 - CONCRETE SHALL BE 3,000 P.S.I.





ADA PARKING SIGN
NTS



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	BA ARCHITECTS 1500 S. MARSH SUIT 200 SAN ANTONIO, TX 78204
LANDSCAPE ARCHITECT	LANDSCAPE 113 S. ALAMO SAN ANTONIO, TX 78205
ENGINEER	LUNY & HUNTER ENGINEERING 113 S. ALAMO SAN ANTONIO, TX 78205
INSPECTOR	INSPECTOR 113 S. ALAMO SAN ANTONIO, TX 78205
DATE	12/14/2019
SCALE	AS SHOWN
TITLE	WFAC Black Box Addition
PROJECT NUMBER	230462
DRAWING NUMBER	

WFAC Black Box Addition PKG 1
 600 S. Milman St.
 San Antonio, TX 78203
 ISSUE FOR CONSTRUCTION




CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION



DETAILS

C1201



ARCHITECT SAN ANTONIO PBK Architects, Inc. P&C
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-9123 P
210-829-0578 F
TX Firm BR 1608

WFCAC Black Box Addition PKG 1
600 S Alhambra St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT Alamo Colleges
DATE 2024/06/12 PROJECT NUMBER 230462

No.	Description	Date
-----	-------------	------

ISSUE FOR CONSTRUCTION

BUILDING NUMBER

DETAILS

C1202

REINFORCING STEEL

LOWER UNIT 10' X 3'-0" (TYPE B)

BAR NO.	SIZE	SPAC.	LENGTH	WEIGHT
A	#4	12"	10'-0"	40
B	#4	12"	4'-0"	16
B ₁	#4	12"	4'-0"	16
B ₂	#4	12"	4'-0"	16
F ₁	#4	12"	10'-0"	40
F ₂	#4	12"	10'-0"	40
F ₃	#4	12"	10'-0"	40
F ₄	#4	12"	10'-0"	40

LOWER UNIT 10' X 5'-0" (TYPE D)

BAR NO.	SIZE	SPAC.	LENGTH	WEIGHT
A	#4	12"	10'-0"	40
B	#4	12"	5'-0"	20
B ₁	#4	12"	5'-0"	20
B ₂	#4	12"	5'-0"	20
F ₁	#4	12"	10'-0"	40
F ₂	#4	12"	10'-0"	40
F ₃	#4	12"	10'-0"	40
F ₄	#4	12"	10'-0"	40

GENERAL NOTES

- REINFORCING STEEL SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE ACI 308R-11 AND EXTENSION TYPE C & D.
- TYPE C & D REINFORCING STEEL SHALL BE PROVIDED WITH 180° BENDS AT ALL CORNERS AND AT ALL CHANGES IN BAR SIZE.
- QUANTITY SHOWN ARE FOR CONSTRUCTION INFORMATION ONLY.
- CONCRETE FOR STRUCTURE SHALL BE CLASS "A" CONCRETE.
- ALL DIMENSIONS RELATING TO REINFORCING STEEL ARE TO CENTER OF BAR.
- ALL REINFORCING STEEL SHALL HAVE A MINIMUM COVER OF 1 1/2".
- ALL REINFORCING STEEL SHALL CONFORM TO ASTM A-618 GRADE 60 REQUIREMENTS.
- ALL CORNER COVERS SHALL BE COVERED 3".
- DEPRESSION SLAB SHALL RECEIVE A WOOD FORM.
- FACE OF INLET TO CONFORM TO FACE OF CURB LINE.
- ALL BARS REINFORCING INLET AND COVER SHALL BE CUT ON BEND.
- FOR ALL REINFORCING BARS, PLACEMENT SHALL BE TO THE OUTSIDE OF FORM AND COVER SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- FOR ALL REINFORCING BARS, PLACEMENT SHALL BE TO THE INSIDE OF FORM AND COVER SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- FOR ALL REINFORCING BARS, PLACEMENT SHALL BE TO THE INSIDE OF FORM AND COVER SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- FOR ALL REINFORCING BARS, PLACEMENT SHALL BE TO THE INSIDE OF FORM AND COVER SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- FOR ALL REINFORCING BARS, PLACEMENT SHALL BE TO THE INSIDE OF FORM AND COVER SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.

PHASE CONSTRUCTION

- THE CURB INLET AND EXTENSION SHALL BE CONSTRUCTED TO A DEPTH TO BEAT THE INLET AND EXTENSION TYPE C & D.
- UPON THE CURB INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.
- UPON THE INLET AND EXTENSION WITH A REINFORCING STEEL APPROVED BY THE ENGINEER AND CONSTRUCT THE INLET AND EXTENSION OVER THE CURB.

CONCRETE INLET BOX CONFIGURATIONS (LOWER UNITS)

MAY 2009
CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT
TYPE "C" INLET (TYPE I & II) & INLET EXTENSION STANDARDS
SHEET 1 OF 3

BAR NO.	SIZE	SPAC.	LENGTH	WEIGHT
A	#4	12"	34"	14
B	#4	12"	24"	10
C	#4	12"	24"	10
D	#4	12"	24"	10
E	#4	12"	24"	10
F	#4	12"	24"	10
G	#4	12"	24"	10
H	#4	12"	24"	10
I	#4	12"	24"	10
J	#4	12"	24"	10
K	#4	12"	24"	10
L	#4	12"	24"	10
M	#4	12"	24"	10
N	#4	12"	24"	10
O	#4	12"	24"	10
P	#4	12"	24"	10
Q	#4	12"	24"	10
R	#4	12"	24"	10
S	#4	12"	24"	10
T	#4	12"	24"	10
U	#4	12"	24"	10
V	#4	12"	24"	10
W	#4	12"	24"	10
X	#4	12"	24"	10
Y	#4	12"	24"	10
Z	#4	12"	24"	10

GENERAL NOTES

- ALL DIMENSIONS ARE SHOWN IN INCHES AND (MILLIMETERS).
- FREE OPEN AREA: 2.75 SQ. FT.
- MATERIAL: CAST GRAY IRON ASTM A-18, CLASS 35B.
- FINISH: NOT PAINTED.
- WEIGHT: 329#.

DATE: 06/24/92

REINFORCING STEEL (FOR Hu=11")

UPPER UNIT EXTENSION (FOR Hu=11")

BAR NO.	SIZE	SPAC.	LENGTH	WEIGHT
A	#4	12"	11'-0"	44
B	#4	12"	4'-0"	16
C	#4	12"	4'-0"	16
D	#4	12"	4'-0"	16
E	#4	12"	11'-0"	44
F	#4	12"	11'-0"	44
G	#4	12"	11'-0"	44
H	#4	12"	11'-0"	44
I	#4	12"	11'-0"	44
J	#4	12"	11'-0"	44
K	#4	12"	11'-0"	44
L	#4	12"	11'-0"	44
M	#4	12"	11'-0"	44
N	#4	12"	11'-0"	44
O	#4	12"	11'-0"	44
P	#4	12"	11'-0"	44
Q	#4	12"	11'-0"	44
R	#4	12"	11'-0"	44
S	#4	12"	11'-0"	44
T	#4	12"	11'-0"	44
U	#4	12"	11'-0"	44
V	#4	12"	11'-0"	44
W	#4	12"	11'-0"	44
X	#4	12"	11'-0"	44
Y	#4	12"	11'-0"	44
Z	#4	12"	11'-0"	44

LOWER UNIT EXTENSION

BAR NO.	SIZE	SPAC.	LENGTH	WEIGHT
A	#4	12"	11'-0"	44
B	#4	12"	4'-0"	16
C	#4	12"	4'-0"	16
D	#4	12"	4'-0"	16
E	#4	12"	11'-0"	44
F	#4	12"	11'-0"	44
G	#4	12"	11'-0"	44
H	#4	12"	11'-0"	44
I	#4	12"	11'-0"	44
J	#4	12"	11'-0"	44
K	#4	12"	11'-0"	44
L	#4	12"	11'-0"	44
M	#4	12"	11'-0"	44
N	#4	12"	11'-0"	44
O	#4	12"	11'-0"	44
P	#4	12"	11'-0"	44
Q	#4	12"	11'-0"	44
R	#4	12"	11'-0"	44
S	#4	12"	11'-0"	44
T	#4	12"	11'-0"	44
U	#4	12"	11'-0"	44
V	#4	12"	11'-0"	44
W	#4	12"	11'-0"	44
X	#4	12"	11'-0"	44
Y	#4	12"	11'-0"	44
Z	#4	12"	11'-0"	44

GENERAL NOTES

- WHEN INLET EXTENSIONS ARE REQUIRED FOR ON SLOPE, THE INLET AND EXTENSION SHALL BE PLACED ON THE UPPER END OF THE SLOPE.
- FOR CURB INLET EXTENSION REINFORCING STEEL, NOTES & DIMENSIONS APPLICABLE TO THE INLET AND EXTENSION SHALL APPLY TO THE INLET AND EXTENSION.

INLET BOLTING DETAILS

UPPER UNIT
LOWER UNIT
SECTION A-A CURB INLET EXTENSION TYPE E
TYPE "CI" INLET WITH INLET EXTENSION BOXES




MAY 2009
CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT
TYPE "C" INLET (TYPE I & II) & INLET EXTENSION STANDARDS
SHEET 2 OF 3

BAR NO.	SIZE	SPAC.	LENGTH	WEIGHT
A	#4	12"	11'-0"	44
B	#4	12"	4'-0"	16
C	#4	12"	4'-0"	16
D	#4	12"	4'-0"	16
E	#4	12"	11'-0"	44
F	#4	12"	11'-0"	44
G	#4	12"	11'-0"	44
H	#4	12"	11'-0"	44
I	#4	12"	11'-0"	44
J	#4	12"	11'-0"	44
K	#4	12"	11'-0"	44
L	#4	12"	11'-0"	44
M	#4	12"	11'-0"	44
N	#4	12"	11'-0"	44
O	#4	12"	11'-0"	44
P	#4	12"	11'-0"	44
Q	#4	12"	11'-0"	44
R	#4	12"	11'-0"	44
S	#4	12"	11'-0"	44
T	#4	12"	11'-0"	44
U	#4	12"	11'-0"	44
V	#4	12"	11'-0"	44
W	#4	12"	11'-0"	44
X	#4	12"	11'-0"	44
Y	#4	12"	11'-0"	44
Z	#4	12"	11'-0"	44

GENERAL NOTES


- FOR LID DESIGN OUTSIDE OF CITY OF SAN ANTONIO, CONSULT WITH MANUFACTURER'S LID ON LID AND RING.
- LOAD BEARING CAPACITY OF 10-20 MINS.
- THE LOAD BEARING CAPACITY SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- THE CHARGED WEIGHT OF THE MANHOLE RING AND COVER SHALL BE AT LEAST 800 LBS.

MAY 2009
CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT
TYPE "C" INLET (TYPE I & II) & INLET EXTENSION STANDARDS
SHEET 3 OF 3



REINFORCING BAR LAP SPICE TABLE (MASONRY), (BEAMS AND COLUMNS), (SLABS AND WALLS). Includes tables for bar size, position, and lap class.

COLUMN SCHEDULE table with columns for MARK, SECT., TOP CONN., BASE PLATE, ANCHORS, SECT., and REMARKS.





Project information including architect (PBK Architects), engineer (Lundy & Franke Engineering), key plan, and notes/sections & details.



ARCHITECT SAN ANTONIO PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216



ENGINEERING 568 HEIMER ROAD San Antonio, TX 78232 PH (210) 979-7900 TX FIRM REG. #3388



CLIENT: Alamo Colleges, DATE: 2024/05/23, PROJECT NUMBER: 230462

ISSUE FOR CONSTRUCTION BUILDING NUMBER AB

DEFERRED SUBMITTALS

Table with columns: BUILDING CONSTRUCTION, YES, NO, DESCRIPTION. Rows include STEEL, CONCRETE, and WOOD.

6. MASONRY CONSTRUCTION CONT. Table with columns: SPECIAL INSPECTIONS NOT REQUIRED PER 1704.5.1, EMPLOYED MASONRY IN NON-ESSENTIAL FACILITIES AND EMPLOYED MASONRY IN ESSENTIAL FACILITIES, IBC 1705.4, QUALIFICATIONS BASED ON ASTM C1093.

7. CONCRETE CONSTRUCTION CONT. Table with columns: PERIODIC, EACH CONCRETE POUR, ACI 318-CH 5.11, 5.13, QUALIFICATIONS BASED ON ASTM C1017.

8. MASONRY CONSTRUCTION CONT. Table with columns: EMPLOYED MASONRY IN NON-ESSENTIAL FACILITIES AND EMPLOYED MASONRY IN ESSENTIAL FACILITIES, IBC 1704.5.3, QUALIFICATIONS BASED ON ASTM C1093.

9. INSPECTION OF FABRICATORS FOR STRUCTURAL STEEL Table with columns: FABRICATION AND IMPLEMENTATION PROCEDURES, IBC 1705.2.1, CWI, ASNT, LICENSED ENGINEER.

Pursuant to IBC Chapter 17 (1704.2.1) provide the following Special Inspector Qualifications to the RDP/RC prior to start of inspections;

- 1. Testing Laboratory Qualifications meeting ASTM0329 and accreditation by AASHTO and/or A2LA, and CCRL of the National Bureau of Standards.
2. Special Inspector's name and proof of meeting the qualification requirements set forth in:
a. ASTM C1077 for concrete,
b. ASTM D3740 for soils,
c. ASTM C1093 for masonry,
d. ASTM D-2922 and D-3017 for Density control of compaction

IBC 1704.2.1 "written documentation demonstrating the competence and relevant experience or training of special inspectors who will perform special inspections and tests during construction. Experience or training shall be considered relevant where the documented experience or training is related in complexity to the same type of special inspection or testing activities for projects of similar complexity and material qualities." These qualifications are in addition to qualifications specified in other sections of the IBC.

TESTING & INSPECTION REQUIREMENTS (INCLUDING SPECIAL INSPECTIONS)

Table with columns: REQUIRED INSPECTION VERIFICATION, FREQUENCY, TYPE AND/OR FREQUENCY OF TESTING, IBC SECTION & REFERENCE CODES, INSPECTOR QUALIFICATIONS. Rows include SOILS (SLAB ON GRADE), CHEMICAL INJECTION, PILE FOUNDATIONS, etc.




ARCHITECT SAN ANTONIO PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216



1801 Marlin Luther King Dr., San Antonio, TX 78203

WFAC Black Box Addition PKG 1 ISSUE FOR CONSTRUCTION




CLIENT: Alamo Colleges, DATE: 2024/05/23, PROJECT NUMBER: 230462. DRAWING HISTORY table with columns: No., Description, Date.

ISSUE FOR CONSTRUCTION

BUILDING NUMBER: AB

SPECIAL INSPECTION NOTES

ISSUE FOR CONSTRUCTION



LA PROJECT NO. 03/215-00
LA FILE NO. WFAC-Blackbox Addition, Structural R23


FOUNDATION PLAN
SCALE: 1/8" = 1'-0"



ARCHITECT
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-5578 F
TX Firm BR 1606

LUNDY & FRANKE
ENGINEERING
548 HEIMER ROAD
SAN ANTONIO, TEXAS 78232
PH 210-879-7900
TX FIRM REG. #3888

WFAC Black Box Addition PKG 1





CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/05/23	230462	
DRAWING HISTORY		
No.	Description	Date
2	City Comments	06/12/24

ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

FOUNDATION FRAMING PLAN

S-201

ISSUE FOR CONSTRUCTION



CMU LINTEL SCHEDULE

SIZE	CLEAR OPENING		REMARKS
	GREATER THAN	UP TO	
ONE COURSE	-	4'-0"	8" BEARING @ EA. END
TWO COURSE	4'-0"	8'-6"	8" BEARING @ EA. END
THREE COURSE	8'-6"	14'-0"	8" BEARING @ EA. END

MASONRY WALL REINFORCEMENT:

MN-1 PROVIDE GROUTED REINFORCED VERTICAL CELLS AND HORIZONTAL BOND BEAMS AT WALL TOP EDGES, CORNERS, FREE ENDS, WINDOW AND DOOR JAMBS, LINTELS AND OTHER LOCATIONS WHERE SHOWN ON ARCHITECTURAL DRAWINGS. REINFORCE EACH GROUTED CELL AND BOND BEAM WITH 1-#4 BAR CONTINUOUS (REINFORCE LINTELS AS SPECIFIED BELOW).

MN-2 BASIC VERTICAL REINFORCEMENT FOR EXTERIOR WALLS SHALL BE #4 @ 32" o.c. (EVERY 4TH VERTICAL CELL).




MN-3 PROVIDE GROUTED REINFORCED LINTELS WITH 8" BEARING EACH END OF ALL DOORS, WINDOWS, AND OTHER OPENINGS. USE ONE-COURSE LINTELS FOR OPENINGS UP TO 4'-0"; TWO-COURSE LINTELS FOR OPENINGS UP TO 8'-6"; THREE-COURSE LINTELS FOR OPENINGS UP TO 14'-0". REINFORCE EACH COURSE WITH 2-#5 BAR CONTINUOUS.

MN-4 PROVIDE MATCHING DOWELS IN FOUNDATION FOR ALL VERTICAL REINFORCEMENT.

MN-5 CMU SHALL HAVE A UNIT STRENGTH OF 1,900 PSI. USE TYPE S MORTAR. REINFORCED CMU SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 7000 PSI. GROUT FOR FILLED CELLS SHALL BE MADE OF CEMENT, SAND AND PEA GRAVEL IN APPROXIMATE RATIO OF 1:3:2 AND SHALL HAVE 28-DAY COMPRESSIVE STRENGTH OF 2,500 PSI.

MN-6 ANCHOR MASONRY TO STRUCTURE AS SHOWN IN DETAILS. SEE SPECIFICATIONS FOR ORDINARY MASONRY ANCHORS INCLUDING DOVETAIL ANCHOR SLOTS IN ADJACENT CONCRETE MEMBERS.

MN-7 LEVEL 1 INSPECTED MASONRY REQUIRES CONTRACTOR TO SUBMIT, AT CONTRACTOR'S COST, COMPRESSIVE WALL DESIGN STRENGTH (FM) VERIFIED BY INDEPENDENT TESTING LAB BY PRISM TESTS BEFORE MASONRY CONSTRUCTION BEGINS. PROVIDE UNIT MASONRY STRENGTH, GROUT MIX DESIGN AND MORTAR MIX DESIGN.



GRADE BEAM SCHEDULE

MARK	W X D*	MAIN REINFORCING	TIES
GB1	12 x 24"	2-#6 x CONT. TOP & BOTTOM	#3 @ 24" o.c.
GB2	18 x 24"	3-#6 x CONT. TOP & BOTTOM	#3 @ 24" o.c.

* REF. NOTE FN-4

FOUNDATION NOTES:

FN-1 5" CONCRETE SLAB REINFORCED W/ #4 @ 12" o.c. EACH WAY IN TOP. SUPPORT AT 4'-0" o.c. EACH WAY WITH CONCRETE BLOCKS OR BRICKS. SUPPORT BOTTOM BEAM REINFORCEMENT AT 4'-0" INTERVALS.

FN-2 15 MIL. POLYOLEFIN VAPOR RETARDER UNLESS NOTES OTHERWISE IN SPECIFICATIONS. AT ALL JOINTS PROVIDE 6" LAPS W/ 4" TAPE.

FN-3 COMPACTED SELECT FILL (SEE UF-6 "UNDERFLOOR FILL NOTES").

FN-4 ALL BEAM SOFFITS SHALL BEAR 24" MINIMUM INTO NATURAL GRADE OR COMPACTED FILL. ON PERIMETER, INCREASE SCHEDULED BEAM DEPTH AS REQUIRED FOR SOFFIT TO BEAR 24" MINIMUM BELOW FINISH GRADE. REF GEOTECHNICAL REPORT. ALL PERIMETER GRADE BEAMS SHALL BEAR ON LIMESTONE.

FN-5 GRADE BEAMS AND SLAB TURNDOWNS SHALL BE FORMED BY WALLS AND SOFFIT OF CAREFULLY SHAPED TRENCH. USE A SMOOTH-MOUTHED BUCKET. IF A TOOTHED BUCKET IS USED, EXCAVATION SHALL BE STOPPED 6" ABOVE FINAL GRADE AND THE REMAINING EXCAVATION ACCOMPLISHED WITH A SMOOTH MOUTHED BUCKET OR BY HAND LABOR TO REMOVE ALL LOOSE SOILS DISTURBED BY THE BUCKET TEETH. WOODFORM EXPOSED FACES TO A DEPTH OF 8" BELOW FINISHED GRADE.

FN-6 AT ALL BEAM CORNERS & T-INTERSECTIONS, PROVIDE 4-#7 X 6'-0" CORNER BARS (2-TOP AND 2-BOTTOM).

FN-7 TRENCHES SHALL BE VERIFIED FOR SIZE TO MAINTAIN CLEARANCES AROUND REINFORCEMENT PRIOR TO PLACING REINFORCEMENT.

FN-8 WHERE BEAM DEPTH EXCEEDS 36", ADD #4 @ 12" o.c. IN EACH FACE OF BEAM.

UNDERFLOOR FILL NOTES:

UF-1 BEFORE ANY CONSTRUCTION IS BEGUN, PERFORM ROUGH GRADING AND CUT SWALES SO THAT GROUNDS WILL DRAIN AWAY FROM THE BUILDING. MAINTAIN DRAINAGE DURING ALL PHASES OF CONSTRUCTION SO THAT STORM WATER WILL BE CONDUCTED AWAY FROM THE BUILDING. KEEP EXCAVATIONS PUMPED FREE OF STORM WATER AT ALL TIMES.

UF-2 PRECAUTIONS SHALL BE TAKEN TO PROTECT OPEN EXCAVATIONS FROM EXCESSIVE LOSS OR GAIN IN NATURAL MOISTURE LEVEL PRIOR TO PLACEMENT OF BASE MATERIAL. KEEP MOIST DURING DRY WEATHER AND KEEP STORM WATER PUMPED OUT, INCLUDING NIGHTS AND WEEKENDS, DURING RAINS.

UF-3 IN THE AREA OCCUPIED BY THE FOUNDATION AND ALL ADJACENT SIDEWALKS, PLUS 3'-0", REMOVE A MINIMUM OF 7'-0" OF TOPSOIL INCLUDING ALL ORGANIC MATERIALS, ROOTS, ETC. FROM THE SITE. DO NOT USE FOR UNDERFLOOR FILL. REMOVE ADDITIONAL MATERIAL AS NECESSARY TO PROVIDE A MINIMUM OF 7'-0" OF SELECT FILL AS PER UF-6.

UF-4 THE RESULTING SURFACE SHALL BE PROOF ROLLED WITH A SUFFICIENTLY HEAVY ROLLER (15 TONS) TO LOCATE AND DENSITY WEAK AND COMPRESSIBLE ZONES. A MINIMUM OF 6 PHASSES OF THE ROLLER IS REQUIRED. ANY SOFT SPOTS SHALL BE REMOVED AND REPLACED WITH COMPACTED SELECT FILL.


UF-5 THE ROLLED SUBGRADE SHALL BE SCARIFIED JUST PRIOR TO FILL PLACEMENT TO A MINIMUM DEPTH OF 6" AND RECOMPACTED TO MINIMUM OF 95% OF THE MAXIMUM DENSITY DETERMINED BY ASTM D698 COMPACTION TEST, MAINTAINING MOISTURE CONTENT BETWEEN -1 AND +3 PERCENTAGE POINTS UNTIL COVERED.

UF-6 FOR A DISTANCE OF 3'-0" OUTSIDE OF THE BUILDING LINE AND ALL ADJACENT SIDEWALKS, AND BEGINNING AT THE LOW END, BUILD UP TO THE ELEVATION OF THE BOTTOM OF THE SLAB WITH SELECT CRUSHED STONE FILL CONFORMING TO TxDOT SPECIFICATIONS, ITEM 247, TYPE "A" GRADE 2. A MINIMUM THICKNESS OF 7'-0" IS REQUIRED. NO DIRT FILL SHALL BE USED UNDER THE BUILDING FOUNDATION. SUBMIT WRITTEN CERTIFICATION OF COMPLIANCE WITH TxDOT, ITEM 247 SPECIFICATIONS BY TEST PERFORMED ON FIELD EXAMPLES.

UF-7 ALL FILL SHALL BE PLACED IN 8" LOOSE HORIZONTAL LIFTS AND COMPACTED TO A MINIMUM OF 95% OF THE MAXIMUM DENSITY AS DETERMINED BY ASTM D698 COMPACTION TEST. MAINTAINING MOISTURE CONTENT BETWEEN -1 AND +3 PERCENTAGE POINTS UNTIL COVERED. EXCESS FILL AT BUILDING PERIMETER SHALL BE CUT AND GRADED TO COMPLY WITH FINISHED GRADE REQUIREMENTS, AND SHALL BE OVERLAID WITH A 1'-0" THICK LAYER OF IMPERVIOUS CLAY FOR A MINIMUM DISTANCE OF 5'-0" FROM BUILDING LINE. REFER TO DETAIL 77.

UF-8 PERFORM ALL EARTH WORK DESCRIBED ABOVE BEFORE TRENCHING FOR GRADE BEAMS OR MECHANICAL LINES.

UF-9 REFERENCE GEOTECHNICAL REPORT BY: ? PROJECT NO. ?, DATED ?.



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-823-5578 F
TX Firm BR 1608


REGISTERED ARCHITECT
MBA ARCHITECTS
1310-002
2015-2019
DESIGNER
T 713-681-8811
LANDSCAPE
HSE AND DESIG
T 713-681-8811
STRUCTURAL
LUNY & FRANK ENGINEERING
T 713-681-8811
MEP
T 713-681-8811
SPECIALTY CONTRACTORS
T 713-681-8811
GENERAL CONTRACTOR
T 713-681-8811

LUNDY & FRANK ENGINEERING
548 HEIMER ROAD PH 018 979-7900
SAN ANTONIO, TEXAS 78232 FX 018 979-7900
TX FIRM REG. #388

WFAAC Black Box Addition PKG 1

1801 Melvin Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT	
Alamo Colleges	PROJECT NUMBER 230462
DATE 2024/05/23	

DRAWING HISTORY

No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTIONS, DETAILS & MECH. YARD FOUNDATION

S-301

ISSUE FOR CONSTRUCTION

LA PROJECT NO.: 09316-00
 LA FILE NO.: WFAC-Blackbox Addition Structural R23



1 SECTION
 1/2" = 1'-0"

EE

W




ARCHITECT	PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-5578 F TX Firm BR 1606
ASSOCIATE ARCHITECT	BA ARCHITECTS 1100 W. Loop West San Antonio, TX 78204
CONSULTANT	LANDSCAPE ROSE AND DESIGN 1111 W. Loop West San Antonio, TX 78204
STRUCTURAL	LUNDY & FRANKE ENGINEERING 548 HEIMER ROAD SAN ANTONIO, TEXAS 78232 PH 210-979-7800 FX 210-979-7800 TX FIRM REG. #3388
MECHANICAL	
ELECTRICAL	
PLUMBING	
BEAM PROFESSIONALS	
MEASUREMENT	
CONSTRUCTION	

LUNDY & FRANKE ENGINEERING
 548 HEIMER ROAD PH 210-979-7800
 SAN ANTONIO, TEXAS 78232 FX 210-979-7800
 TX FIRM REG. #3388

WFAC Black Box Addition PKG 1

1801 Main, Luther King Dr.,
 San Antonio, TX 78203
 ISSUE FOR CONSTRUCTION





CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
2024/05/23		
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	

SECTION

S-302

ISSUE FOR CONSTRUCTION



LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-8Blackbox Addition - Structural R23

1 SECTION
3/8" = 1'-0"



ARCHITECT
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-823-0123 P
210-823-5578 F
TX Firm BR 1606

ASSOCIATE ARCHITECT
M&A ARCHITECTS
1200 W. 15th St.
San Antonio, TX 78205
210-223-8888

CONTRACTOR
LUNDEY & FRANK ENGINEERING
1200 W. 15th St.
San Antonio, TX 78205
210-223-8888


MECHANICAL
PROVISIONS
BEAM PROFESSIONALS
1200 W. 15th St.
San Antonio, TX 78205
210-223-8888



WFAC Black Box Addition PKG 1

1801 Main St., Lumber King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



DATE: 06/12/2024

SHAWN J. FRANKE
82639
LICENSED PROFESSIONAL ENGINEER

CLIENT	Alamo Colleges
DATE	2024/05/23
PROJECT NUMBER	230462

No.	Description	Date

ISSUE FOR CONSTRUCTION


BUILDING NUMBER AB

SECTION

S-303

ISSUE FOR CONSTRUCTION

LA PROJECT NO.: 03/515-00
LA FILE NO.: WFAC-38blackbox Addition, Structural R23



1 SECTION
3/8" = 1'-0"





ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-823-0123 P 210-823-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA ARCHITECTS
OWNER	ALAMO COLLEGES
DESIGNER	LUNDY & FRANKE ENGINEERING
TRACER	TRACER
LANDSCAPE	LANDSCAPE
ROOF AND DRIP	ROOF AND DRIP
STRUCTURAL	STRUCTURAL
LUNDY & FRANKE ENGINEERING	LUNDY & FRANKE ENGINEERING
MEP	MEP
TRACER	TRACER
PROVIDOR	PROVIDOR
BEAM PROFESSIONALS	BEAM PROFESSIONALS
MEASUR	MEASUR
TRACER	TRACER
TRACER	TRACER



WFAC Black Box Addition PKG 1

1801 Melvin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER **AB**

SECTION

S-304

ISSUE FOR CONSTRUCTION

1"


LA PROJECT NO.: 09316-00
 LA FILE NO.: WFAC-3blackbox Addition Structural R23

11.2 11.1

10.1

9.1

REF. PLAN



1 SECTION
 1/2" = 1'-0"




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1808	
ASSOCIATE ARCHITECT	BA ARCHITECTS
OWNER	
DESIGNER	
LANDSCAPE	
ROOF AND CEILING	
STRUCTURAL	
MECHANICAL	
ELECTRICAL	
PLUMBING	
HAZARDOUS WASTE	
TRAVEL	



WFAC Black Box Addition PKG 1

1801 Mathis Luther King Dr.
 San Antonio, TX 78203
 ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION

BUILDING NUMBER	AB
-----------------	----

SECTION
 S-305

ISSUE FOR CONSTRUCTION

0'
1'



1 SECTION
1/2" = 1'-0"



LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-Blackbox Addition - Structural R23



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-823-0123 P
210-823-5578 F
TX Firm BR 1606

LUNDY & FRANKE
ENGINEERING
548 HEIMER ROAD PH 018 979-7900
SAN ANTONIO, TEXAS 78232 FX 210 979-7800
TX FIRM REG. #3388

WFAC Black Box Addition PKG 1



CLIENT
Alamo Colleges
DATE 2024/05/23 PROJECT NUMBER 230462

No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTION

S-306


ISSUE FOR CONSTRUCTION

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-38blackbox Addition: Structural R23



2 SECTION
3/8" = 1'-0"

NOT USED



1 SECTION
1/2" = 1'-0"





ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-5578 F
TX Firm BR 1606

LUNDY & FRANKE ENGINEERING
548 HEIMER ROAD
SAN ANTONIO, TEXAS 78232
TX FIRM REG. #3388

WFAC Black Box Addition PKG 1


1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION




CLIENT Alamo Colleges		
DATE 2024/05/23	PROJECT NUMBER 230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	

SECTIONS
S-307


ISSUE FOR CONSTRUCTION



3 SECTION
3/4" = 1'-0"



2 SECTION
3/4" = 1'-0"



1 SECTION
3/4" = 1'-0"

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-3blackbox Addition - Structural R23





ARCHITECT	PBK Architects, Inc.
SAN ANTONIO	
601 N.W. Loop 410, Suite 400	
San Antonio, TX 78216	
210-820-0123 P	
210-829-5578 F	
TX Firm BR 1606	
ASSOCIATE ARCHITECT	BA ARCHITECTS
1311 S. W. Loop 410, Suite 400	
San Antonio, TX 78216	
210-820-0123 P	
210-829-5578 F	
TX Firm BR 1606	
CONSULTANT	LUNDY & FRANKE ENGINEERING
540 HEIMER ROAD	
SAN ANTONIO, TEXAS 78232	
PH: 210-979-7900	
FX: 210-979-7800	
TX FIRM REG. #3388	



WFAC Black Box Addition PKG 1

1801 Main, Luther King Dr.,
San Antonio, TX, 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/05/23	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	




SECTIONS

S-308

ISSUE FOR CONSTRUCTION

1'

LA PROJECT NO.: 09/315-00
LA FILE NO.: WFAC-3blackbox Addition; Structural R23




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-4123 P. 210-829-5578 F. TX Firm BR 1606	
ASSOCIATE ARCHITECT	MAX ARCHITECTS
CONTRACTOR	CONTRACTOR
DESIGNER	DESIGNER
LANDSCAPE	LANDSCAPE
ROOF AND GROUND	ROOF AND GROUND
STRUCTURAL	STRUCTURAL
LUNDY & FRANKE ENGINEERING	LUNDY & FRANKE ENGINEERING
MECHANICAL	MECHANICAL
ELECTRICAL	ELECTRICAL
PLUMBING	PLUMBING
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL

LUNDY & FRANKE ENGINEERING
548 HEIMER ROAD PH. (210) 979-7900
SAN ANTONIO, TEXAS 78232 FX. (210) 979-7800
TX FIRM REG. #3388

WFAC Black Box Addition PKG 1

1801 Main, Luther King Dr.,
San Antonio, TX, 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
2024/05/23		
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	

SECTIONS & DETAILS

S-309



CONCRETE WALL NOTES:

- CW-1** UNLESS SHOWN OTHERWISE, AT CORNERS, ANGLE BENDS, AND AT JUNCTION WITH OTHER WALLS, LAP ALL HORIZONTAL BARS PER REINFORCING BAR LAP SCHEDULE.
- CW-2** UNLESS SHOWN OTHERWISE, WHERE WALLS STOP, POSITION TWO (2) OF THE WALL VERTICAL BARS AT THE END OF THE WALL, PROVIDED THAT VERTICAL BARS ARE #6 OR LARGER. IF WALL VERTICAL BARS ARE SMALLER THAN #6, USE 3#6 AT WALL VERTICAL BARS. PROVIDE #4 U-BARS (60 DIAMETER LAPS) ENCLOSEING VERTICAL BARS AT END FACES, SAME SPACING AS HORIZONTAL BARS.
- CW-3** UNLESS SHOWN OTHERWISE, ADD 2#6 BARS IN EACH FACE OVER OPENING, EXTENDING 60 DIAMETERS BEYOND LIMITS OF OPENING, AND ADD 2#6X5'-0" PLACED DIAGONALLY AT EACH CORNER OF OPENING. PROVIDE #4 U-BARS (60 DIAMETER LAPS) AT END FACES FOR EACH BAR (HORIZONTAL OR VERTICAL) INTERRUPTED BY OPENING. U-BARS SHALL ENCLOSE HORIZONTAL OR VERTICAL BARS AT OPENING. NOTIFY A/E PRIOR TO FABRICATION AND CONSTRUCTION FOR OPENINGS LARGER THAN 2'-0"x2'-0".
- CW-4** UNLESS SHOWN OTHERWISE, USING REINFORCING BAR LAP SCHEDULE LAP WALL DOWELS FROM BEAM OR FOOTING TO MATCH THE SIZE AND SPACING OF ALL VERTICAL BARS IN WALL ABOVE. EXTEND INTO WALL USING REINFORCING BAR LAP SCHEDULE. AT CONSTRUCTION JOINTS, EITHER CONTINUE ALL VERTICAL BARS PROVIDE LAPS OF ALL VERTICAL BARS INTO WALL ABOVE USING REINFORCING BAR LAP SCHEDULE.

CONCRETE WALL SCHEDULE						
MK	THICKNESS	VERTICAL BARS		HORIZONTAL BARS		REMARKS
		I.S. FACE	O.S. FACE	I.S. FACE	O.S. FACE	
CW-1	12"	#5 @ 10"o.c.	#5 @ 10"o.c.	#4 @ 12"o.c.	#4 @ 12"o.c.	4000PSI REF. CW-NOTES

1st FLOOR CONCRETE BEAM SCHEDULE

MARK	SIZE		MAIN REINFORCING								STIRRUPS			REMARKS
	W	D	TOP BARS		BOTTOM BARS		TOP BARS AT SUPPORT				SIZE	TYPE	SPACING AT EACH END OF BEAM	
			REINF.	TYP.	REINF.	TYP.	REINF.	TYP.	SUPP.					
B1	30	24 5/8	4#8	T1	3#8	B1	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B2	30	24 5/8	4#8	T1	3#8	B1	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B3	30	24 5/8	4#6	T2	3#8	B6	-	-	-	#4	U	1 @ 2.10 @ 10 BAL @ 24"o.c.		
B4	30	24 5/8	4#6	T3	3#8	B3	-	-	-	#4	U	1 @ 2.10 @ 10 BAL @ 24"o.c.		
B5	30	24 5/8	4#6	T3	3#8	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B6	30	24 5/8	4#6	T2	3#8	B6	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B7	48	24 5/8	4#9	T2	3#9	B6	-	-	-	#4	U	1 @ 2.15 @ 10 BAL @ 24"o.c.		
B8	48	24 5/8	4#9	T3	3#9	B4	-	-	-	#4	U	1 @ 2.15 @ 10 BAL @ 24"o.c.		
B9	48	24 5/8	4#9	T3	3#9	B3	-	-	-	#4	U	1 @ 2.15 @ 10 BAL @ 24"o.c.		
B10	48	24 5/8	4#9	T2	3#9	B6	-	-	-	#4	U	1 @ 2.10 @ 10 BAL @ 24"o.c.	EXTEND HOOK END INTO CANT.	
B11	48	24 5/8	4#9	T6	3#9	B3	-	-	-	#4	U	1 @ 2.10 @ 10 BAL @ 24"o.c.	CANTILEVER	
B12	48	24 5/8	4#9	T2	3#9	B6	-	-	-	#4	U	1 @ 2.10 @ 10 BAL @ 24"o.c.		
B13	48	24 5/8	4#9	T2	3#9	B6	-	-	-	#4	U	1 @ 2.12 @ 10 BAL @ 24"o.c.		
B14	48	24 5/8	4#9	T3	3#9	B3	-	-	-	#4	U	1 @ 2.12 @ 10 BAL @ 24"o.c.		
B15	48	24 5/8	4#9	T3	3#9	B8	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B16	48	24 5/8	4#9	T2	3#9	B1	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B17	48	24 5/8	4#9	T3	3#9	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B18	48	24 5/8	4#9	T3	3#9	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B19	48	24 5/8	4#9	T1	3#9	B1	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.	CANTILEVER	
B20	48	24 5/8	4#9	T3	3#9	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B21	48	24 5/8	4#9	T2	3#9	B6	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B22	30	24 5/8	4#7	T2	3#8	B6	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B23	30	24 5/8	4#7	T3	3#8	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B24	30	24 5/8	4#7	T3	3#8	B4	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B25	24	24 5/8	4#6	T2	3#8	B6	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B26	24	24 5/8	4#6	T3	3#8	B4	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B27	24	24 5/8	4#6	T3	3#8	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B28	12	24 5/8	2#6	T2	2#8	B6	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B29	12	24 5/8	2#6	T3	2#8	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B30	30	24 5/8	4#6	T1	3#8	B1	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B31	30	24 5/8	4#6	T2	3#8	B7	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.	EXTEND HOOK END INTO CANT.	
B32	30	24 5/8	4#6	T3	3#8	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B33	30	24 5/8	4#6	T6	4#8	B5	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.	CANTILEVER	
B34	24	24 5/8	4#6	T1	2#8	B1	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B35	48	24 5/8	4#6	T1	3#8	B1	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B36	24	24 5/8	4#6	T1	2#8	B8	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B37	24	24 5/8	4#6	T1	2#8	B8	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B38	48	24 5/8	4#7	T2	3#8	B6	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		
B39	48	24 5/8	4#7	T3	3#8	B3	-	-	-	#4	U	1 @ 2.6 @ 10 BAL @ 24"o.c.		




ARCHITECT PRK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-5578 F
TX Firm BR 1606



ENGINEERING
568 HEIMER ROAD
SAN ANTONIO, TEXAS 78232
TX FIRM REG. #3388

WFAC Black Box Addition PKG 1
 1801 Marlin Luther King Dr.,
 San Antonio, TX, 78203
 ISSUE FOR CONSTRUCTION




CLIENT Alamo Colleges	
DATE 2024/05/23	PROJECT NUMBER 230462
DRAWING HISTORY	
No.	Description
ISSUE FOR CONSTRUCTION	
BUILDING NUMBER	AB


CONC. BEAM SCHED & NOTES

S-401


1st FLOOR CONCRETE JOIST SCHEDULE															
MARK	SIZE			MAIN REINFORCING						STIRRUPS			REMARKS		
	W	D	SECT.	SPCG.	TOP BARS		BOTTOM BARS		TOP BARS AT SUPPORT		SIZE	NO. LEGS		SPACING AT EACH END OF JOIST	
					REINF.	TYP.	REINF.	TYP.	REINF.	TYP.	SUPP.				
J1	6	20		6'-0"	2-#6	T2	1-#8	B6	-	-	-	#4	10	11" O.C.	
J2	6	20		6'-0"	1-#8	T3	1-#8	B3	-	-	-	#4	10	11" O.C.	
J3	6	20		6'-0"	1-#6	T1	1-#6	B1	-	-	-	#4	8	11" O.C.	




5 DETAIL TYP. SECT. @ REINF. BM. SCALE: 3/4" = 1'-0"




6 DETAIL TYP. SECT. @ INT. BM. SCALE: 3/4" = 1'-0"




7 DETAIL TYP. ALLOWABLE CONDUIT PLACEMENT SCALE: 3/4" = 1'-0"




1 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"




2 DETAIL TYP. SLAB REINF. @ ACCESS HATCH SCALE: 3/4" = 1'-0"



3 DETAIL TYP. SLAB SECT. @ FLR. DROP SCALE: 3/4" = 1'-0"



4 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"



5 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"


- CONCRETE JOIST NOTES:**
- CJ-1 STEEL PAN-JOIST FORMS SHALL BE SPACED SO THAT JOISTS IN ADJACENT SPANS ARE IN EXACT ALIGNMENT UNLESS SHOWN OTHERWISE. NARROWER WIDTH FORMS SHALL BE COORDINATED WITH BASIC SPACING WHERE MAKE-UPS ARE REQUIRED.
 - CJ-2 WHERE STIRRUPS ARE SCHEDULED, (1) 6-LEG LADDER STIRRUP ASSEMBLY WITH VERTICAL LEGS AT 11" O.C. IS THE MINIMUM. IF SCHEDULE CALLS FOR MORE THAN 6 LEGS, USE A COMBINATION OF LADDER STIRRUP ASSEMBLIES TO PROVIDE REQUIRED NUMBER OF LEGS AT SPACING SCHEDULED.
 - CJ-3 JOIST TOP BARS SHALL BE SUPPORTED ON 1" DIA. X 1'-0" SUPPORT BARS PLACED ON 3/4" BAR CHAIRS ACROSS PAN FORMS AT 4'-0" O.C. TIED TO STIRRUPS BEGINNING AT FIRST LEG.
 - CJ-4 BEAM STEEL SHALL HAVE CLEARANCE OF 1-1/2" TO STIRRUPS AT BOTTOM AND SIDES BUT 2-1/2" AT TOP. JOIST STEEL SHALL HAVE CLEARANCE OF 1-1/2". THEREFORE, REINFORCEMENT SHALL BE PLACED IN THE FOLLOWING SEQUENCE:
 1. PLACE ALL BEAM BARS.
 2. PLACE BOTTOM JOIST BARS.
 3. PLACE SUPPORT BARS (NOTE CJ-3).
 4. PLACE TOP JOIST BARS.
 5. PLACE EXTRA SLAB BARS (NOTE CJ-7).
 6. PLACE WELDED WIRE FABRIC.
 - CJ-5 REINFORCE SLAB WITH 4x4-W3.5x3.5 WELDED WIRE FABRIC, LAPPED 1-1/2 MESHES AT SPLICES. DRAPE OVER TOP JOIST BARS AND TIE DOWN SECURELY IN BOTTOM OF SLAB MIDWAY BETWEEN JOISTS. 3/4" OFF BOTTOM WITH BAR CHAIRS AND TIED TO FROM AT 24" O.C. MESH SHALL EXTEND OVER THE ENTIRE WIDTH OF BEAMS.
 - CJ-6 WHERE FLOOR DROPS (DEPRESSIONS) OCCUR, ADJUST PAN FORMS SO THAT SLAB THICKNESS IS MAINTAINED AS SHOWN IN DETAILS.
 - CJ-7 WHERE JOIST RUN PARALLEL TO BEAMS OR WALLS, PROVIDE #3 DOWELS AT 2'-0" O.C. AT EDGE BEAMS ONLY. (SEE DETAIL).
 - CJ-8 UNLESS SPECIFICALLY SHOWN ON FRAMING PLANS, JOISTS SHALL NOT BE INTERRUPTED OR REDUCED IN CROSS SECTIONAL AREAS WITHOUT ENGINEER'S APPROVAL.
 - CJ-9 IF VERTICAL MECHANICAL SLEEVE PROJECTS INTO A JOIST BY MORE THAN 1-1/2", WIDEN JOIST BY USING NEXT SMALLER PAN WIDTH FOR A DISTANCE OF 4'-0" BOTH SIDES OF SLEEVE AND FIELD DRAPE BARS AROUND SLEEVES (NO TORCHING).
 - CJ-10 CONDUITS IN 4-1/2" SLABS SHALL NOT BE LARGER THAN 1" DIAMETER, WHERE CONDUIT IS PARALLEL (OR NEARLY PARALLEL) TO JOIST, DO NOT LOCATE IN CENTER THIRD OF SLAB SPAN.
 - CJ-11 PROVIDE 6" WIDE BRIDGING JOIST WHERE INDICATED "BJ" ON PLAN. REINFORCE WITH 1-#6 CONTINUOUS TOP AND BOTTOM AND ANCHOR INTO TERMINAL BEAMS WITH #6 X 5'-0" CORNER BAR TOP AND BOTTOM.
 - CJ-12 WHERE PARTITIONS RUNNING PARALLEL TO JOISTS ARE DESIGNATED BY THE SYMBOL ON THE FRAMING PLAN, OR NOTED ON ARCHITECTURAL DRAWINGS, ADD #4 X 6'-0" AT 9" O.C. FOR ENTIRE LENGTH OF JOIST SPAN, IN BOTTOM OF SLAB ON 3/4" BAR CHAIRS, RUNNING PERPENDICULAR TO JOISTS FROM JOIST CENTERLINE TO JOIST CENTERLINE.



ARCHITECT SAN ANTONIO
 PBK Architects, Inc.
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-820-0123 P
 210-829-5578 F
 TX Firm BR 1606

ENGINEERING
LUNDY & FRANKE
 ENGINEERING
 568 HEIMER ROAD
 SAN ANTONIO, TEXAS 78232
 PH. (210) 979-7900
 TX FIRM REG. #3388

WFAC Black Box Addition PKG 1




CLIENT Alamo Colleges
 DATE 2024/05/23 PROJECT NUMBER 230462

No.	Description	Date

ISSUE FOR CONSTRUCTION
 BUILDING NUMBER AB

CONC. JOIST SCHED,
 NOTES & DETAILS




GENERAL SITE DEMOLITION NOTES

- DEMOLITION PLANS INDICATE SOME OF THE SCOPE OF WORK INVOLVED FOR THE DEMOLITION PHASE OF THIS PROJECT. CONTRACTOR SHALL REVIEW ALL SHEETS FOR ADDITIONAL DEMOLITION SCOPE.
- CONTRACTOR SHALL VERIFY EXISTING SITE AND BUILDING CONDITIONS AND DIMENSIONS IN THE FIELD PRIOR TO DEMOLITION ACTIVITIES AND WORK.
- CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY DISCREPANCIES IN WRITING.
- CONTRACTOR SHALL NOTIFY ARCHITECT AND OWNER OF ANY POSSIBLE ASBESTOS CONTAINING MATERIALS DISCOVERED BEFORE PROCEEDING WITH WORK. PROTECT INTERIOR CONSTRUCTION TO REMAIN DURING DEMOLITION AND CONSTRUCTION.
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS BEFORE COMMENCING WORK.
- AFTER AWARD OF THE CONTRACT, CHANGE ORDER REQUESTS FOR ADDITIONAL MONEY WILL NOT BE APPROVED IF THE WORK COULD HAVE BEEN ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR.
- CONTRACTOR SHALL NOT SCALE DRAWINGS.
- CONTRACTOR SHALL PROVIDE ALL NECESSARY TEMPORARY SHORING, TEMPORARY BRACING, AND OR TEMPORARY SUPPORTS AS REQUIRED TO MAINTAIN STRUCTURAL INTEGRITY OF EXISTING STRUCTURE TO REMAIN AND OR EXISTING BUILDING ELEMENTS TO REMAIN.
- CONTRACTOR IS TO VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES PRIOR TO DEMOLITION ACTIVITIES AND WORK.
- CONTRACTOR SHALL REMOVE TRASH AND DEBRIS REGULARLY AS NECESSARY TO ELIMINATED INTERFERENCE WITH ROADS, STREET, WALKS, AND ALL OTHER ADJACENT FACILITIES.
- CONTRACTOR SHALL REMOVE TRASH AND DEBRIS FROM THE SITE ON A DAILY BASIS.
- CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION OF TEMPORARY DUST AND OR SOUND PARTITION BETWEEN CONSTRUCTION AREA AND AREAS NOT IN SCOPE AS NECESSARY. DEMOLITION ACTIVITIES SHALL BE PERFORMED SO AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY AND OCCUPANTS (I.E. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST).
- CONTRACTOR SHALL REPAIR, REPLACE, OR PATCH EXISTING BUILDINGS, DRIVEWAYS, SIDEWALKS, CANOPIES, AND OR PARKING AREAS DAMAGED, MODIFIED, AND OR DISTURBED BY DEMOLITION WORK AT NO COST TO THE OWNER.
- ALL EXISTING EQUIPMENT THAT REMAINS SHALL BE PROTECTED DURING DEMOLITION AND OR CONSTRUCTION TO PREVENT DAMAGE. ANY DAMAGE TO REMAINING EXISTING EQUIPMENT SUSTAINED DURING DEMOLITION AND OR CONSTRUCTION SHALL BE EQUIVALENTLY REPLACED OR EQUIVALENTLY REPAIRED AT NO COST TO THE OWNER.
- CONTRACTOR SHALL PROVIDE TRAFFIC HANDLING MEASURES TO PROTECT THE GENERAL PUBLIC AT ALL TIMES, AS NECESSARY AND AS REQUIRED BY AUTHORITIES HAVING JURISDICTION.
- DO NOT INTERRUPT EXISTING UTILITIES, EXCEPT WHEN AUTHORIZED IN WRITING BY AUTHORITIES HAVING JURISDICTION. PROVIDE TEMPORARY SERVICES DURING INTERRUPTIONS TO EXISTING UTILITIES AS ACCEPTABLE TO AUTHORITIES HAVING JURISDICTION.
- WHEN UTILITY SERVICES ARE REQUIRED TO BE REMOVED, RELOCATED, OR ABANDONED, PROVIDE BYPASS CONNECTIONS TO MAINTAIN CONTINUITY OF SERVICE BEFORE PROCEEDING WITH DEMOLITION.
- CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES INCLUDING BUT NOT LIMITED TO THE FOLLOWING: ELECTRIC, GAS, WATER, TELEPHONE, STORM SEWER, AND SANITARY SEWER FOR FIELD LOCATION OF ALL UNDERGROUND AND OVERHEAD UTILITY LINES. PRIOR TO COMMENCEMENT OF ANY DEMOLITION WORK, CONTRACTOR SHALL IDENTIFY ALL ELECTRICAL CIRCUITS SERVICING THE AREA INVOLVED WITH THIS DEMOLITION. THOSE CIRCUITS SHALL THEN BE LOCKED OUT AND TAGGED OUT IF THEY DO NOT SERVICE ANY OF THE REMAINING BUILDING. THOSE CIRCUITS WHICH ARE IDENTIFIED TO SERVICE BOTH THE AREA TO BE DEMOLISHED AND THE REMAINING BUILDING SHALL BE SPLIT SO AS TO KILL ALL ELECTRICAL POWER TO THE AREA TO BE DEMOLISHED WHILE MAINTAINING POWER TO THE REMAINDER OF THE BUILDING.
- CONTRACTOR SHALL RELOCATE UTILITIES AND EQUIPMENT AS REQUIRED TO ACCOMMODATE NEW HVAC, ELECTRICAL, PLUMBING, AND TECHNOLOGY REQUIREMENTS FOR NEW WORK.
- PROTECT EXISTING SITE ELEMENTS AND EXISTING LANDSCAPING TO REMAIN. PROTECTION SHALL INCLUDE BUT NOT BE LIMITED TO EXISTING TREES AND OTHER EXISTING VEGETATION INDICATED TO REMAIN IN PLACE AGAINST UNNECESSARY CUTTING, BREAKING, OR SKINNING OF ROOTS, SKINNING OR BRUISING OF BARK, SMOTHERING OF TREES BY STOCKPILING CONSTRUCTION MATERIAL OR EXCAVATED MATERIAL WITHIN DRIP LINES.
- CONTRACTOR SHALL REGRADE AND HYDROMULCH AREAS AFFECTED BY DEMOLITION.
- OWNER HAS RIGHT OF FIRST REFUSAL OF ALL ITEMS REMOVED AS PART OF THE SCOPE OF WORK, WHETHER IDENTIFIED AS SALVAGE OR NOT.
- NOTIFY THE BUILDING OWNER OF ANY MATERIALS, FIXTURES, ETC. TO BE REMOVED THAT ARE DESIRED SALVAGEABLE. TURN OVER ANY REQUESTED ITEMS TO THE BUILDING OWNER IN GOOD AND CLEAN CONDITION.
- ALL FURNITURE WILL BE REMOVED OR RELOCATED BY THE OWNER AS NECESSARY PRIOR TO THE DEMOLITION WORK OF THIS PROJECT. CONTRACTOR SHALL COORDINATE WITH OWNER AS REQUIRED.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO	
601 N.W. Loop 410, Suite 400	
San Antonio, TX 78216	
210-820-0123 P	
210-820-0578 F	
TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
1100 S. W. Loop 410, Suite 400	
San Antonio, TX 78216	
210-820-0123 P	
210-820-0578 F	
TX Firm BR 1608	
ARCHITECT	LANE & FRANK ENGINEERING
1100 S. W. Loop 410, Suite 400	
San Antonio, TX 78216	
210-820-0123 P	
210-820-0578 F	
TX Firm BR 1608	


WFAC Black Box Addition PKG 1



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/14	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1
DEMOLITION ARCHITECTURAL SITE PLAN


SITE DEMOLITION PLAN LEGEND



06 DEMOLITION SITE PLAN
1" = 20'-0"

ISSUE FOR CONSTRUCTION

FOR BLUEBAM LABELING CO.



GENERAL ARCH SITE PLAN NOTES

- REFER TO CIVIL DOCUMENTS.
- COORDINATE ALL SPOT ELEVATIONS AND DIMENSIONS WITH CIVIL, LANDSCAPE, AND OR STRUCTURAL DOCUMENTS.
- PROVIDE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 1% MINIMUM, 2% MAXIMUM AT ALL EXTERIOR PAVED PEDESTRIAN AREAS, INCLUDING BUT NOT LIMITED TO SIDEWALKS, PATIOS, STAIRS, PAVING, U.N.O.
- PROVIDE AND INSTALL POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 5% FOR A HORIZONTAL DISTANCE OF 10 FEET AT ALL EXTERIOR NON-PAVED AREAS U.N.O.
- REFER TO CIVIL DOCUMENTS FOR CONCRETE SIDEWALK EXPANSION JOINTS AND CONCRETE SIDEWALK CONTROL JOINTS.
- VERIFY AND CONFIRM ALL JOINT LAYOUTS AT ALL CONCRETE SIDEWALKS WITH ARCHITECT PRIOR TO POURING OF CONCRETE.
- PROVIDE AND INSTALL CONCRETE SIDEWALK EXPANSION JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT 50 FEET ON-CENTER MAX. U.N.O.
- PROVIDE AND INSTALL CONCRETE SIDEWALK CONTROL JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT DISTANCES EQUIVALENT TO SIDEWALK WIDTH, BUT NOT TO EXCEED 10 FEET ON-CENTER MAX.
- VERIFY ALL SITE SIGNAGE LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION OF SITE SIGNAGE.



ARCHITECT PBK Architects, Inc.
 SAN ANTONIO
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1808

PROJECT
 WFAC Black Box Addition PKG 1
 1801 Martin Luther King Dr.,
 San Antonio, TX 78203

ISSUE FOR CONSTRUCTION

ALAMO COLLEGES
 ST. PHILIP'S COLLEGE


BRICK QUANTITY TAKEOFF

LISTED AREAS ARE ACTUAL SQ. FT. TAKE-OFF FORM FROM THE PACKAGE 2
 60% CD SET. GC TO ORDER OVERAGE/WASTE AS REQUIRED.

ORANGE BRICK - 12,200 SF
 WHITE BRICK - 2,275 SF

IF SPANDREL REPLACEMENT FOR BRICK VE OPTION IS SELECTED
 ADDED BRICK COUNT

ORANGE BRICK - 490 SF
 WHITE BRICK - 155 SF



ARCH SITE PLAN LEGEND

- EXISTING BUILDING
- NOT IN SCOPE
- NEW BUILDING / ADDITION
- GRASS
- SIDEWALK
- TOP CAST CONCRETE; RE. LANDSCAPE
- SALT FINISH CONCRETE; RE. LANDSCAPE




CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE 2024/06/14	230462	
DRAWING HISTORY		
No.	Description	Date
1	ASI #1 - CITY & OWNER COMMENTS	6-14-2024

ISSUE FOR CONSTRUCTION


BUILDING NUMBER 1

ARCHITECTURAL SITE PLAN


AS100




30 EXTERIOR SLIDING GATE 1/4" = 1'-0"
29 GATE JAMB 1 1/2" = 1'-0"
28 GATE TO FENCE 1 1/2" = 1'-0"
27 GATE AND FENCE WALL CONNECTION 1 1/2" = 1'-0"




24 NORTH EQUIPMENT ELEVATION 1/4" = 1'-0"




18 EQUIPMENT ELEVATION NORTH 1/4" = 1'-0"




12 EQUIPMENT ELEVATION SOUTH 1/4" = 1'-0"



06 EQUIPMENT ELEVATION EAST 1/4" = 1'-0"



15 CMU WALL SECTION 1 1/2" = 1'-0"



03 EQUIPMENT ENCLOSURE 3/32" = 1'-0"

GENERAL ARCH SITE PLAN NOTES

- REFER TO CIVIL DOCUMENTS.
- COORDINATE ALL SPOT ELEVATIONS AND DIMENSIONS WITH CIVIL, LANDSCAPE, AND/OR STRUCTURAL DOCUMENTS.
- PROVIDE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 1% MINIMUM, 2% MAXIMUM AT ALL EXTERIOR PAVED PEDESTRIAN AREAS, INCLUDING BUT NOT LIMITED TO SIDEWALKS, PATIOS, STAIRS, PAVING, U.N.O.
- PROVIDE AND INSTALL POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 5% FOR A HORIZONTAL DISTANCE OF 10 FEET AT ALL EXTERIOR NON-PAVED AREAS U.N.O.
- REFER TO CIVIL DOCUMENTS FOR CONCRETE SIDEWALK EXPANSION JOINTS AND CONCRETE SIDEWALK CONTROL JOINTS.
- VERIFY AND CONFIRM ALL JOINT LAYOUTS AT ALL CONCRETE SIDEWALKS WITH ARCHITECT PRIOR TO POURING OF CONCRETE.
- PROVIDE AND INSTALL CONCRETE SIDEWALK EXPANSION JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT 50 FEET ON-CENTER MAX. U.N.O.
- PROVIDE AND INSTALL CONCRETE SIDEWALK CONTROL JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT DISTANCES EQUIVALENT TO SIDEWALK WIDTH, BUT NOT TO EXCEED 10 FEET ON-CENTER MAX.
- VERIFY ALL SITE SIGNAGE LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION OF SITE SIGNAGE.

KEYNOTE LEGEND

NUMBER	DESCRIPTION
04 05 00 CDP	CAVITY DRAINAGE MATERIAL
04 05 00 TIE	TIE SYSTEM
04 05 00 WWV	WICKING WEEP
04 20 00 BK1	BRICK TYPE 1 - FIELD
04 20 00 BK2	BRICK TYPE 2 - WHITE ACCENT
04 20 00 CBB	CMU BOND BEAM
04 20 00 CUB (R)	8" CMU - RUNNING BOND


ARCH SITE PLAN LEGEND

- EXISTING BUILDING
- NOT IN SCOPE
- NEW BUILDING / ADDITION
- GRASS
- SIDEWALK
- TOP CAST CONCRETE, RE. LANDSCAPE
- SALT FINISH CONCRETE, RE. LANDSCAPE



ARCHITECT: SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-820-0578 F
TX Firm BR 1608
PBK.com








WFAC Black Box Addition PKG 1



CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE: 2024/06/14	230462	
DRAWING HISTORY		
No.	Description	Date
1	ASI #1 - CITY & OWNER COMMENTS	6-14-2024

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1
ARCHITECTURAL ENLARGED SITE PLANS

AS401



GENERAL ARCH PLAN NOTES

- DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TAKE PRECEDENCE. CONTACT ARCH FOR CLARIFICATION IS NECESSARY IN ORDER TO DETERMINE THE INTENT OF THE CONTRACT DOCUMENTS.
- DRAWINGS NOTED AS "N.T.S." OR "N.T.S." ARE NOT TO SCALE.
- ALL DIMENSIONS ARE TO STRUCTURAL COLUMN LINES OR THE SURFACE OF PARTITION ASSEMBLY U.N.O.
- FIELD VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS BEFORE COMMENCING WORK. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH AFFECTED WORK.
- NOTES OR DIMENSIONS NOTED AS "TYPICAL" OR "TYP." OR "TYP." SHALL APPLY TO CONDITIONS THAT ARE THE SAME OR SIMILAR.
- DIMENSIONS NOTED AS "FIELD VERIFY" OR "V.I.F." OR "V.I.P." SHALL BE MEASURED AND CONFIRMED AT THE PROJECT SITE BY THE CONTRACTOR AND REVIEWED WITH THE ARCH. BEFORE INCORPORATING INTO THE WORK.
- DIMENSIONS NOTED AS "CLEAR" OR "CLEAR INSIDE" OR "CLR" REQUIRE SPECIFIC COORDINATION AMONG DISCIPLINES AND OR MANUFACTURERS.
- REFER TO PARTITION TYPES ON A-800 SERIES SHEETS.
- ALL INTERIOR PARTITIONS THIS SHEET, EXCEPT FOR FURR-OUT PARTITIONS, SHALL BE PARTITION TYPE _S8_ U.N.O.
- ALL INTERIOR FURR-OUT PARTITIONS THIS SHEET SHALL BE PARTITION TYPE _F3_ U.N.O.
- ADJOIN FINISHED FACE OF WALLS WHERE WALL PARTITIONS OF DIFFERING THICKNESS ABUT AND OR ADJOIN IN THE SAME PLANE.
- PROVIDE AND INSTALL CONTINUOUS REVEAL TRIM AT JOINT WHERE GYPSUM BOARD WALL PARTITIONS ABUT AND OR ADJOIN MASONRY WALL PARTITIONS IN THE SAME PLANE.
- ALL INTERIOR CMU OUTSIDE CORNERS SHALL HAVE BULLNOSE U.N.O.
- ALL DOORS SHALL BE SET 4 INCHES OFF THE ADJACENT PERPENDICULAR WALL ON THE HINGE SIDE OF THE DOOR U.N.O. NOTIFY ARCH. OF ANY DOOR-RELATED CONFLICTS, INCLUDING BUT NOT LIMITED TO CONFLICTS CONCERNING ACCESSIBILITY STANDARDS.
- ALL DOOR THRESHOLDS AT ALL EXTERIOR DOORS SHALL BE SET IN FULL BED OF SEALANT.
- COORDINATE ALL ROOF DRAIN LEADER LOCATIONS WITH FLOOR PLAN PRIOR TO FLOOR SLAB CONSTRUCTION.
- ALL FLOOR SLOPES TO FLOOR DRAINS SHALL NOT EXCEED 1:48.
- PROVIDE AND INSTALL SELF-LEVELING UNDERLAYMENT WHERE UNEVEN FLOOR SLAB EXISTS PRIOR TO INSTALLATION OF FLOOR FINISHES.
- COORDINATE HOUSEKEEPING PAD LOCATIONS AND DIMENSIONS WITH EQUIPMENT TO BE INSTALLED.
- ALL FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS U.N.O.
- ALL FLOOR FINISH MATERIAL CHANGES SHALL HAVE REDUCER STRIPS.
- ALL REQUIRED ACCESSIBLE CLEARANCES FOR ALL ITEMS, INCLUDING BUT NOT LIMITED TO ALL COUNTER TOPS, ALL PLUMBING FIXTURES, ALL DRINKING FOUNTAINS, ALL ELECTRIC WATER COOLERS, ALL LAVATORIES, ALL URINALS, ALL TOILETS SHALL BE STRICTLY ENFORCED.
- APPLY BITUMINOUS COATING TO ALL CONCEALED STRUCTURAL STEEL MEMBERS AT ALL EXTERIOR CANOPY LOCATIONS.
- REFER TO OTHER DISCIPLINE DOCUMENTS FOR ADDITIONAL SCOPE OF WORK.




ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400	San Antonio, TX 78216
210-829-0133 P	210-829-0578 F
TX Firm BR 1608	
ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400	San Antonio, TX 78216
210-829-0133 P	210-829-0578 F
TX Firm BR 1608	

WFAC Black Box Addition PKG 1

1801 Martin Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



FLOOR FINISH LEGEND

(Pattern)	CONCRETE GRADE BEAM, RE. STRUCT.
(Pattern)	MUD SLAB AREA
(Pattern)	EXISTING BUILDING

CLIENT		
Alamo Colleges	PROJECT NUMBER	
2024/06/14	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	1	

CRAWLSPACE FLOOR PLAN - COMPOSITE

A-100

FOR BLUEBAM LABELING CO. A-811

DOOR SCHEDULE PANEL AND FRAME TYPES

ISSUE FOR CONSTRUCTION

0"
1"

DOOR SCHEDULE - PKG1										
MARK	ROOM NAME	PHASE	PAIR	PANEL				FRAME		
				WIDTH	HEIGHT	TYPE	MATERIAL	GLASS	TYPE	FINISH
LEVEL 01										
159	BLACKBOX	New Construction	PAIR	14' - 0"	12' - 0"	SCU		N	00UE	PAINTED STEEL

MATERIALS	
AL - ALUMINUM	VL - VINYL
HM - HOLLOW METAL	PL - PLASTIC LAMINATE
HG - HOLLOW METAL GALV	WS - WOOD, SOLID CORE
HS - HM 24 GA. STEEL	WH - WOOD, HOLLOW CORE
SS - STAINLESS STEEL	PTDF - PAINTED TYPE

REMARKS LEGEND
1. WITH EGRESS DEVICE
2. MAGNETIC DOOR HOLDER
3. FIRE DOOR
4. ELEVATOR MACHINE ROOM DOORS
5. ELECTRICAL ROOM DOORS
6. KICK PLATE ON BOTH SIDES
7. ACCESS PANEL DOOR
8. WITH CLOSER




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1808	
ASSOCIATE ARCHITECT	BAA ARCHITECTS
OWNER	ALAMO COLLEGES
DESIGNER	ALAMO COLLEGES
LANDSCAPE	ALAMO COLLEGES
ROSE AND DESIGN	ALAMO COLLEGES
STRUCTURAL	ALAMO COLLEGES
LINDBY & FRANKS ENGINEERING	ALAMO COLLEGES
MER	ALAMO COLLEGES
MEP	ALAMO COLLEGES
ENVIRONMENTAL	ALAMO COLLEGES
MECHANICAL	ALAMO COLLEGES
ELECTRICAL	ALAMO COLLEGES
PLUMBING	ALAMO COLLEGES
PAINTING	ALAMO COLLEGES
CONSTRUCTION	ALAMO COLLEGES

WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203


ISSUE FOR CONSTRUCTION




CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/14	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	1	

DOOR SCHEDULE PANEL AND FRAME TYPES

A-811



00UE SOUND CONTROL DOOR FRAME
1/4" = 1'-0"




SCU SOUND CONTROL UN-EQUAL LEAFS
1/4" = 1'-0"

File Path: Autodesk Docs://Alamo CS_230462_Al Philip College WEB Add/230462 WFAC - Blackbox Addition - A03.rvt

CHECKED BY:
Checker
DRAWN BY:
Author
Plot Stamp:
6/13/2024 4:32:51 PM

ISSUE FOR CONSTRUCTION



KEYNOTES ALL

- M1 4" CHWS/R PIPING ROUTED FROM EXISTING CAMPUS LOOP VAULT BELOW FLOOR SLAB. REFER TO M-101D FOR CONTINUATION
- M2 APPROXIMATE LOCATION OF EXISTING CHILLED WATER LOOP VAULT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P43

1 MECHANICAL AND PLUMBING SITE PLAN
SCALE: 1" = 20'-0"

File Path: Autodeskt Dcs://Name CS_230462_A1 Philip College WBB AddP23 WFAC- Blackbox Addition -A03.rvt
CHECKED BY: [Blank]
Checked By: [Blank]
DRAWN BY: [Blank]
Author: [Blank]
Plot Stamp: 6/12/2024 4:05:39 PM





ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-0578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	BLA ARCHITECTS 2025 210-820-0123 P 210-829-0578 F TX Firm BR 1608
DESIGNER	TJL 210-820-0123 P 210-829-0578 F TX Firm BR 1608
LANDSCAPE	LANDSCAPE 210-820-0123 P 210-829-0578 F TX Firm BR 1608
MECHANICAL	LUNNEY & FRANKS ENGINEERING 210-820-0123 P 210-829-0578 F TX Firm BR 1608
ELECTRICAL	MEP 210-820-0123 P 210-829-0578 F TX Firm BR 1608
PROVIDOR	MEAN PROJECT SIGNALS 210-820-0123 P 210-829-0578 F TX Firm BR 1608
MEASURER	MEASURER 210-820-0123 P 210-829-0578 F TX Firm BR 1608



WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	06/14/2024	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1


MECHANICAL AND PLUMBING SITE PLAN

MPS-101

ISSUE FOR CONSTRUCTION

File Path: Autodesk Docs://Alamo CS_230462_Al Philip College WBB Add#E23 WFAC - Blackbox Addition - A23.rvt

CHECKED BY:
Checker
DRAWN BY:
Author
Plot Stamp:
6/13/2024 12:25:09 PM



- DEMO SITE PLAN GENERAL NOTES:**
- COORDINATE ROUTING FOR ALL UNDERGROUND ELECTRICAL BRANCH CIRCUITS AND FEEDERS WITH OTHER DISCIPLINES PRIOR TO TRENCHING.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES CAUSED BY INSTALLATION OF NEW WORK.

- SITE PLAN KEYED NOTES:**
- EXISTING ELECTRICAL MANHOLE.
 - EXISTING ELECTRICAL MANHOLE SHALL BE DEMOLISHED AND RELOCATED.
 - EXISTING UNDERGROUND ELECTRICAL DUGBANK WITH 4 EXISTING CONDUITS TO BE REROUTED FOR NEW BLACK BOX EXPANSION.
 - CONTRACTOR TO VERIFY NEW CONSTRUCTIONS DOES NOT OVERLAP EXISTING PARKING LOT LIGHTING. IF NEW CONSTRUCTIONS OVERLAPS EXISTING FEEDER FOR PARKING LOT LIGHTING, EXISTING FEEDERS FOR SITE LIGHTING SHALL BE RELOCATED.
 - EXISTING CONDENSING UNIT SHALL BE RELOCATED. DISCONNECT AND CONDUCTORS SHALL BE REROUTED. UTILIZE EXISTING CIRCUIT. COORDINATE EXACT LOCATION WITH MECHANICAL DRAWINGS.
 - EXISTING DISTRIBUTION MAIN SERVICE DISCONNECT DP-6 FOR ADJACENT WATSON FINE ARTS BUILDING.
 - EXISTING CONDUITS FROM DP-6 TO WATSON'S FINE ARTS BUILDING SHALL BE RELOCATED TO ACCOMMODATE NEW BUILDING. CONTRACTOR SHALL VERIFY PATH WAY AND RELOCATED CONDUITS AND CONDUCTORS TO NEW AVAILABLE LOCATION WITHOUT IMPEDE ANY OTHER SERVICES.
 - EXISTING UTILITY TRANSFORMER FOR WATSON FINE ARTS.
 - EXISTING PARKING LOT FIXTURES SHALL BE DEMOLISHED. CONTRACTOR SHALL PRESERVE CIRCUIT RUN FOR ANY EXISTING FIXTURES REMAINING OR TIED TO DEMOLISHED FIXTURES.
 - EXISTING PEDESTRIAN LOT FIXTURES SHALL BE RELOCATED. CONTRACTOR SHALL PRESERVE CIRCUIT RUN FOR ANY EXISTING FIXTURES REMAINING OR TIED TO DEMOLISHED FIXTURES.





ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 1100 N. LOOP WEST SUITE 1000 SAN ANTONIO, TEXAS 78207 210-454-0000
ENGINEER	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203
LANDSCAPE	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203
MECHANICAL	LUNY & FRANK ENGINEERING 1100 N. LOOP WEST SUITE 1000 SAN ANTONIO, TEXAS 78207 210-454-0000
ELECTRICAL	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203
PLUMBING	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203
MECHANICAL	LEAF ENGINEERS 1801 Main Luther King Dr., San Antonio, TX 78203



WFAC Black Box Addition PKG 1

1801 Main Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
06/14/2024		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER 1

DEMO SITE POWER PLAN


EDS-101

ISSUE FOR CONSTRUCTION

File Path: Autodesk Docs://Alamo CS_230462_Alt Phillip College WEB Add#E23 WFAC - Blackbox Addition - A23.rvt

CHECKED BY:
 Checker
 DRAWN BY:
 Author
 Plot Stamp:
 6/13/2024 12:24:01 PM

5'
 1'



- ELECTRICAL ONE-LINE DIAGRAM NOTES:**
- # INDICATES GENERAL NOTE.
 - ④ INDICATES KEYED NOTE.
 - 1. REFER TO RISER DIAGRAM FOR FEEDER WIRE / CONDUIT SIZES AND FOR ALL FEEDER SIZES NOT SHOWN ON THIS SHEET.
 - 2. 1 #3/0 COPPER GROUND CONDUCTOR IN 1" CONDUIT TO MAIN INCOMING METAL WATER PIPE, TO MAKE GROUNDING ELECTRODE AND TO BUILDING GROUND.
 - 3. NEC 285 SURGE PROTECTIVE DEVICE. RE: DIVISION 26 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
 - 4. ST. PHILLIPS COLLEGE PROVIDED UTILITY TRANSFORMER. CONTRACTOR SHALL COORDINATE WITH ST. PHILLIPS COLLEGE FOR TRANSFORMER NOMENCLATURE.





ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	PKA ARCHITECTS
DESIGNER	DESIGNER
LANDSCAPE	LANDSCAPE
STRUCTURAL	STRUCTURAL
Mechanical	Mechanical
Electrical	Electrical
MECHANICAL ENGINEERING	MECHANICAL ENGINEERING
ELECTRICAL ENGINEERING	ELECTRICAL ENGINEERING
PLUMBING	PLUMBING
MECHANICAL PROFESSIONALS	MECHANICAL PROFESSIONALS
ELECTRICAL PROFESSIONALS	ELECTRICAL PROFESSIONALS
MECHANICAL	MECHANICAL
PLUMBING	PLUMBING
DATE	2/28/21/2023



WFAC Black Box Addition PKG 1

1801 Main Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION




CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
06/14/2024	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
 BUILDING NUMBER 1

ELECTRICAL
 ONE-LINE DIAGRAM

E-501

5
1



- ELECTRICAL ONE-LINE DIAGRAM NOTES:**
- # INDICATES GENERAL NOTE.
 - Ⓢ INDICATES KEYED NOTE.
1. UNLESS NOTED OTHERWISE, ALL TRANSFORMERS TO BE 480/208/120 VOLT 3P, 4W.
 2. PROVIDE THRU-FEED LUGS FOR ALL MULTI-SECTION PANELBOARDS.
 3. REFERENCE ONE-LINE DIAGRAM.
 4. 1#6 G, 3/4"C.
 5. SURGE PROTECTIVE DEVICE, RE: DIVISION 26 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
 6. PER LOCAL NEC STANDARDS.
 7. PROVIDE (2) 3-1/2" CONDUITS WITH PULL STRING(S) STUBBED 5' OUTSIDE OF THE MAIN BUILDING FOR FUTURE USE.

ALUMINUM FEEDER SCHEDULE				
TAG NUMBER	CONDUCTOR QUANTITY AND SIZE	CONDUIT SIZE	SETS	COMMENTS
200	3#250, 1#4G	2"	1	
200N	4#250, 1#4G	2 1/2"	1	
225	3#300, 1#2G	2 1/2"	1	
225N	4#300, 1#2G	3"	1	
250	3#350, 1#2G	2 1/2"	1	
250N	4#350, 1#2G	3"	1	
300	3#500, 1#2G	3"	1	
300N	4#500, 1#2G	3"	1	
400	3#250, 1#1G	2 1/2"	2	
400N	4#250, 1#1G	2 1/2"	2	
600	3#500, 1#2OG	3"	2	
600N	4#500, 1#2OG	3 1/2"	2	
800	3#400, 1#3OG	3"	3	
800N	4#400, 1#3OG	3"	3	
1200	3#500, 1#3OG	3"	4	
1200N	4#500, 1#3OG	3 1/2"	4	

FEEDER SCHEDULE				
TAG NUMBER	CONDUCTOR QUANTITY AND SIZE	CONDUIT SIZE	SETS	COMMENTS
30N	4#10, 1#10G	1"	1	
50N	4#6, 1#10G	1"	1	
60N	4#6, 1#10G	1"	1	
100	3#1, 1#6G	1 1/2"	1	
100N	4#1, 1#6G	1 1/2"	1	
125	3#1, 1#6G	1 1/2"	1	
125N	4#1, 1#6G	2"	1	
150	3#1/0, 1#6G	1 1/2"	1	
150N	4#1/0, 1#6G	2"	1	
175	3#2/0, 1#6G	2"	1	
175N	4#2/0, 1#6G	2"	1	
200	3#3/0, 1#6G	2"	1	
200N	4#3/0, 1#6G	2"	1	
225	3#4/0, 1#4G	2"	1	
225N	4#4/0, 1#4G	2 1/2"	1	
250	3#250, 1#4G	2 1/2"	1	
250N	4#250, 1#4G	3"	1	
300	3#350, 1#4G	3"	1	
300N	4#350, 1#4G	3"	1	
400	3#3/0, 1#3G	2"	2	
400N	4#3/0, 1#3G	2"	2	
400S	4#500	3 1/2"	1	
600	3#350, 1#1G	3"	2	
600N	4#350, 1#1G	3"	2	
600S	4#350	3"	2	
800	3#500, 1#1OG	3"	2	
800N	4#500, 1#1OG	3 1/2"	2	
800S	4#500	3 1/2"	2	
1000	3#400, 1#2OG	3"	3	
1000N	4#400, 1#2OG	3"	3	
1000S	4#400	3"	3	
1200	3#250, 1#3OG	3"	4	
1200N	4#250, 1#3OG	3"	4	
1200S	4#250	3"	4	
1600S	4#400	3"	5	
2000S	4#400	3"	6	
2500S	4#500	3 1/2"	7	
3000S	4#500	3 1/2"	8	
4000S	4#500	3 1/2"	11	



TRANSFORMER FEEDER SCHEDULE				
TAG NUMBER	CONDUCTOR QUANTITY AND SIZE	CONDUIT SIZE	SETS	COMMENTS
P15	3#10, 1#10G	3/4"	1	
S15	4#6, 1#6G	1 1/2"	1	
K15	3#4, 1#6N, 1#6G	1 1/4"	1	
G15	1#6G	1/2"	1	
P15	2#6, 1#10G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
S15	3#4, 1#6G	1 1/2"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G15	1#6G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P25	2#6, 1#10G	1"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
D25	3#1, 1#6G	1 1/2"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G25	1#6G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P30	3#6, 1#10G	3/4"	1	
S30	4#1, 1#6G	1 1/2"	1	
K30	3 #1/0, 1#2/0N, 1#6G	2"	1	
G30	1#6G	1/2"	1	
P37	2#1, 1#6G	1 1/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
D37	3#3/0, 1#4G	3"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G37	1#4G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P45	3#4, 1#6G	1"	1	
S45	4#1/0, 1#6G	1 1/2"	1	
K45	3#2/0, 1#250, 1#4G	2"	1	
G45	1#6G	1/2"	1	
P50	2#1, 1#6G	1 1/4"	1	
S50	3#3/0, 1#3G	2"	1	
G50	1#3G	3/4"	1	
P75	3#1, 1#6G	1 1/2"	1	
S75	4#4/0, 1#2G	2 1/2"	1	
K75	3#4/0, 2#3/0N, 1#2G	2 1/2"	1	
G75	1#1/0G	1/2"	1	
P75	2#3/0, 1#6G	2"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
S75	3#3/0, 1#4G	2"	2	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G75	1#4G	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P75A	3#1, 1#6G	1 1/2"	1	FOR 480 3Ø: 120/240 3Ø TRANSFORMERS
S75A	4#4/0, 1#2G	2 1/2"	1	FOR 480 3Ø: 120/240 3Ø TRANSFORMERS
G75A	1#2/0	1/2"	1	FOR 480 3Ø: 120/240 3Ø TRANSFORMERS
P112	3#2/0, 6G	2"	1	
S112	4#3/0, 1#10G	2"	2	
K112	3#4/0, 1#350N, 1#1/0G	2 1/2"	2	
G112	1#1/0G	3/4"	1	
P150	3#250, 1#4G	2 1/2"	1	
S150	4#350, 1#2OG	3"	2	
K150	3#350, 2#3/0N, 1#2OG	3"	2	
G150	1#2OG	3/4"	1	
P167	2#4/0, 1#2OG	2"	2	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
S167	3#350, 1#3OG	3"	3	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
G167	1#3OG	3/4"	1	FOR 480 1Ø: 120/240 1Ø TRANSFORMERS
P225	3#500, 3#3G	3"	1	
S225	4#350, 1#2OG	3"	1	
K225	3#350, 2#4/0, 1#1G	3 1/2"	3	
G225	1#2OG	3/4"	1	



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-5578 F
TX Firm BR 1608



WFAC Black Box Addition PKG 1
1801 Main Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

ELECTRICAL RISER DIAGRAM

ELECTRICAL SYMBOL LEGEND

Legend table with categories: CIRCUIT RELATED, LIGHTING, CONTROL, POWER OUTLETS, TELEPHONE/DATA, EQUIPMENT. Includes symbols for lighting fixtures, switches, outlets, and equipment with their respective descriptions.

GENERAL ELECTRICAL REMODEL NOTES

- UNLESS SPECIFICALLY INDICATED ON THE DRAWINGS OR OTHERWISE INSTRUCTED BY THE ARCHITECT, ELECTRICAL OUTLETS SHALL HAVE THE FOLLOWING MOUNTING HEIGHTS. DIMENSIONS ARE TO CENTER OF BOX UNLESS OTHERWISE NOTED. WALL SWITCHES, WALL CONVENIENCE RECEPTACLES, WALL DATA/VOICE OUTLETS, WALL OUTLETS FOR WALL MTD. TELEPHONE, WALL CLOCK OUTLETS, MANUAL FIRE ALARM PULL STATIONS, FIRE ALARM SPEAKER/HORN, INTERIOR BELLS BUZZERS, HORNS, SPECIAL PURPOSE WALL OUTLETS, PUSH BUTTONS, ADA VISUAL ALARM.

GENERAL ELECTRICAL NOTES

- UNLESS SPECIFICALLY INDICATED ON THE DRAWINGS OR OTHERWISE INSTRUCTED BY THE ARCHITECT, ELECTRICAL OUTLETS SHALL HAVE THE FOLLOWING MOUNTING HEIGHTS. DIMENSIONS ARE TO CENTER OF BOX UNLESS OTHERWISE NOTED. WALL SWITCHES, WALL CONVENIENCE RECEPTACLES, WALL DATA/VOICE OUTLETS, WALL OUTLETS FOR WALL MTD. TELEPHONE, WALL CLOCK OUTLETS, MANUAL FIRE ALARM PULL STATIONS, FIRE ALARM SPEAKER/HORN, INTERIOR BELLS BUZZERS, HORNS, SPECIAL PURPOSE WALL OUTLETS, PUSH BUTTONS, ADA VISUAL ALARM.


- UNLESS SPECIFICALLY INDICATED ON THE ELECTRICAL DRAWINGS, OUTLETS LOCATED AT COUNTERS AND CABINETS SHALL BE MOUNTED AS SHOWN ON ARCHITECTURAL DETAILS AND ELEVATIONS, OR AS DIRECTED BY ARCHITECT. COORDINATE MOUNTING HEIGHTS AND DETAILS OF ALL OUTLETS (POWER, SIGNAL, ETC.) WITH ARCHITECTURAL CASEWORK DRAWINGS PRIOR TO DIVISION 26 ROUGH-IN. PROVIDE COORDINATION DRAWINGS IN ACCORDANCE WITH DIVISION 26 SPECIFICATIONS WHERE CONFLICTS EXIST. OBTAIN APPROVAL FROM ARCHITECT BEFORE ELECTRICAL ROUGH-IN WHEN CONFLICTS ARISE. REFER TO MECHANICAL DRAWINGS FOR EXACT LOCATION OF ALL HVAC AND PLUMBING EQUIPMENT. CIRCUITING.

LIGHTING FIXTURE NOTES



- KEY TO NOTE PREFIXES: "G" NOTES ARE "GENERAL" LIGHTING NOTES THAT APPLY TO THE ENTIRE PROJECT. "S" NOTES ARE "SCHEDULE" NOTES THAT APPLY TO SPECIFIC LUMINAIRES. REFER TO ARCHITECTURAL REFLECTED CEILING PLANS, ELEVATIONS, SECTIONS, AND DETAILS FOR THE EXACT LOCATION OF ALL LUMINAIRES. ARCHITECTURAL PLANS SHALL GOVERN FOR LOCATION AND LAYOUT. IF ARCHITECTURAL AND ELECTRICAL DRAWINGS CONFLICT IN EXACT COUNT OR FIXTURE TYPE, PROVIDE THE GREATER QUANTITY OR COST TYPE UNLESS OTHERWISE INSTRUCTED. REFER TO DIVISION 26 ELECTRICAL SPECIFICATIONS FOR ADDITIONAL LUMINAIRE AND ELECTRICAL REQUIREMENTS (LENS, AIR HANDLING CHARACTERISTICS, T-BAR CLIPS, BALLAST, LAMPS, TIME FRAME FOR SUBMITTAL OF SUBSTITUTE LIGHT FIXTURES FOR PRIOR APPROVAL, ETC.). FOR EACH SCHEDULED LUMINAIRE, PROVIDE ALL REQUIRED APPURTENANCES FOR INSTALLATION IN APPLICABLE STRUCTURE OR SPECIFIED ARCHITECTURAL EILING. ALL LUMINAIRES SHALL HAVE THE APPROPRIATE NEMA TYPE FRAME THAT IS COMPATIBLE WITH THE CEILING SYSTEM SPECIFIED BY THE ARCHITECT. ELECTRICAL DRAWINGS DO NOT INDICATE CEILING TYPES. CONTRACTOR SHALL REFER TO ARCHITECTURAL PLANS TO DETERMINE CEILING TYPE (GRID, FLANGE, SPLINE, SCREW SLOT, ETC.) AND PROVIDE APPROPRIATE FRAME. EXIT SIGNS AND OTHER LUMINAIRES SHALL NOT BE SUPPORTED BY CEILING TILE. PROVIDE MOUNTING FRAME OR HANGERS TO SECURELY FASTEN IN PLACE ALL LUMINAIRES MOUNTED IN CEILING TILE. FRAMING MEMBERS OF A SUSPENDED CEILING SYSTEM MAY BE USED WHERE DESIGNED FOR THE PURPOSE AND INSTALLED PER NEC 410-16(c). WHERE A SURFACE-MOUNTED LUMINAIRE CONTAINING A BALLAST IS TO BE INSTALLED ON COMBUSTIBLE LOW-DENSITY CELLULOSE FIBERBOARD, IT SHALL BE LISTED FOR THIS CONDITION OR SHALL BE SPACED NOT LESS THAN 1 1/2 INCHES FROM THE SURFACE OF THE FIBERBOARD (NEC 410-76(b)). REQUEST FOR SUBSTITUTION SHALL FOLLOW SPECIFIED PROCEDURES AND SHALL INCLUDE A WORKING SAMPLE SUITABLE FOR TABLE TOP EXAMINATION. UNLESS OTHERWISE NOTED, MOUNT EXIT SIGN DIRECTLY ABOVE EGRESS DOOR (MAXIMUM 24" ABOVE DOOR). PROVIDE WALL MOUNT EXIT SIGNS IN HIGH CEILING AREAS. PROVIDE WINDOW MULLION MOUNTING WITH CONCEALED WIRING WHERE REQUIRED. COORDINATE EXACT ELEVATION WITH ARCHITECT PRIOR TO ROUGH-IN.

CONTACTOR SCHEDULE table with columns: DESIGNATION, CIRCUITS SERVED, CONTACT AMPS, N.O. POLES, COIL VOLTS, CONTROL, SUPPLY CKT., REMARKS. Row 1: C1, 1HA-6, 20, 2, 277, DDC, 1HA-6, ASCO 918 REMOTE CONTROL SWITCH.


1 PROVIDE ASCO ACCESSORY 47 SOLID STATE TWO-WIRE CONTROL INTERFACE MODULE.




8 GROUNDING COMPRESSION CONNECTIONS
NOT TO SCALE





6 GROUND BUS DETAIL
NOT TO SCALE




7 GROUND ROD ASSEMBLY
NOT TO SCALE



- KEYED NOTES:**
- 1 REQUIRES BURNDY Y750 PRESS WITH U99 FOR INSTALLATION.
 - 2 CRIMP CONNECTOR, #2 TO 250 KCMIL TO 3/4\"/>





1 CONDUIT PENETRATION DETAIL - EXTERIOR WALL
NOT TO SCALE



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO	
601 N.W. Loop 410, Suite 400	
San Antonio, TX 78216	
210-820-0123 P	
210-829-5578 F	
TX Firm BR 1608	
ASSOCIATE ARCHITECT	BA ARCHITECTS
DESIGNER	BA ARCHITECTS
LANDSCAPE ARCHITECT	BA ARCHITECTS
MECHANICAL ENGINEER	BA ARCHITECTS
ELECTRICAL ENGINEER	BA ARCHITECTS
PLUMBING ENGINEER	BA ARCHITECTS
MECHANICAL ENGINEER	BA ARCHITECTS
PLUMBING ENGINEER	BA ARCHITECTS
MECHANICAL ENGINEER	BA ARCHITECTS
PLUMBING ENGINEER	BA ARCHITECTS
MECHANICAL ENGINEER	BA ARCHITECTS
PLUMBING ENGINEER	BA ARCHITECTS



WFAC Black Box Addition PKG 1
 1801 Main Luther King Dr.,
 San Antonio, TX 78203
 ISSUE FOR CONSTRUCTION




CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
06/14/2024	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION

ELECTRICAL DETAILS

2 ISOLATED GROUND DETAIL
NOT TO SCALE



3 GROUND WELL ASSEMBLY
NOT TO SCALE



GENERAL NOTES

- CONDUCTOR SIZES SHOWN ARE MINIMUM AND MAY BE LARGER THAN THE MINIMUM SIZES REQUIRED BY NEC.
- INSTALL GROUNDING CONNECTIONS TO BUILDING STRUCTURE AND WATER PIPES AT LOCATIONS THAT ARE VISIBLE AND ACCESSIBLE FOR INSPECTION, MAINTENANCE, AND TESTING.
- INSTALL AN INSULATED THROAT GROUNDING BUSHING ON EACH METALLIC SERVICE ENTRANCE CONDUIT. BOND TO GROUND BUS USING CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE PHASE CONDUCTOR SIZE.
- INSTALL AN INSULATED THROAT GROUNDING BUSHING ON EACH METALLIC FEEDER CONDUIT. BOND TO GROUND BUS USING CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.122 USING THE FEEDER CIRCUIT OVERCURRENT DEVICE SIZE OR THE SEPARATELY DERIVED SYSTEM OVERCURRENT DEVICE SIZE.
- BOND HOT AND COLD WATER PIPING SYSTEMS.

KEYED NOTES


- INSTALL GROUND (NEUTRAL) CONDUCTOR SAME SIZE AS THE LARGEST PHASE CONDUCTOR IF THE LINE-TO-NEUTRAL LOAD EXCEEDS 5% OF THE CONNECTED LOAD. IF NEUTRAL LOAD IS SMALLER, INSTALL THE NEC MINIMUM GROUNDING CONDUCTOR.
- INSTALL GROUNDING ELECTRODE CONDUCTOR, SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE PHASE CONDUCTOR SIZE, BUT NOT SMALLER THAN 2 AWG UNLESS NOTED OTHERWISE.
- INSTALL EQUIPMENT GROUNDING CONDUCTOR SIZED BASED ON NEC TABLE 250.122 USING THE FEEDER OVERCURRENT DEVICE SIZE.
- BOND TO GAS PIPE ON THE BUILDING SIDE OF THE GAS METER.
- INSTALL GROUNDING ELECTRODE CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SEPARATELY DERIVED SYSTEM PHASE CONDUCTOR SIZE.
- INSTALL A CONCRETE-ENCASED MAIN GROUNDING ELECTRODE IN THE BUILDING FOUNDATION AROUND THE ENTIRE PERIMETER OF THE BUILDING. LOCATE ELECTRODE IN THE BOTTOM ONE-THIRD OF THE FOUNDATION WITH AT LEAST 3 INCHES OF CONCRETE COVER. USE EITHER OF THE FOLLOWING MATERIALS FOR THE ELECTRODE:

BARE COPPER CABLE NOT SMALLER THAN THE GROUNDING ELECTRODE CONDUCTOR REQUIRED BY THE NEC AND NOT SMALLER THAN 2 AWG. REFER SPEC 28 05 26.

BARE OR GALVANIZED REBARS THAT ARE MADE ELECTRICALLY CONTINUOUS USING COPPER JUMPERS NOT SMALLER THAN THE NEC REQUIRED GROUNDING ELECTRODE CONDUCTOR AND NOT SMALLER THAN 4 AWG. USE REINFORCING BARS NOT SMALLER THAN THE FOLLOWING BASED ON THE TOTAL LENGTH OF THE INTERCONNECTED AND PARALLELED REBARS:

TOTAL LENGTH	MINIMUM REBAR SIZE
112 FT	1 3/8" (#1 BAR)
150 FT	1" (#6 BAR)
192 FT	3/4" (#6 BAR)
223 FT	5/8" (#6 BAR)
268 FT	1/2" (#4 BAR)
- BOND PERIMETER STRUCTURAL STEEL COLUMNS TO THE CONCRETE-ENCASED MAIN GROUNDING ELECTRODE. USE CANNULD CONNECTION TO ATTACH GROUNDING ELECTRODE CONDUCTOR TO BASE OF STEEL COLUMN. REFER SPEC 28 05 26.
- INSTALL A 'MAIN GROUND ELECTRODE GROUND BAR' FOR SINGLE POINT GROUNDING. LOCATE AT AN ACCESSIBLE AND VISIBLE POINT NEAR THE SERVICE ENTRANCE EQUIPMENT. MAKE CONNECTIONS TO THE GROUND BAR USING TWO-HOLE COMPRESSION SPADE LUGS THAT MEET IEEE 837 REQUIREMENTS. LABEL EACH CONNECTION TO THE GROUND BAR.
- LIGHTNING PROTECTION GROUNDING COUNTERPOISE - 3/0 AWG COPPER (IF LIGHTING PROTECTION SYSTEM IS SPECIFIED IN PROJECT, RE: SECTION 26 41 00).
- IF LIGHTNING PROTECTION SYSTEM IS SPECIFIED IN PROJECT (26 41 00), BOND THE LIGHTNING PROTECTION SYSTEM GROUNDING COUNTERPOISE TO THE MAIN GROUND ELECTRODE GROUND BAR. USE 4/0 AWG COPPER CABLE WITH 600 VOLT INSULATION. AT THE UNDERGROUND CONNECTION USE A COMPRESSION CONNECTOR THAT MEETS IEEE 837 REQUIREMENTS OR USE AN EXOTHERMIC WELD.
- USE THE 'MAIN GROUNDING ELECTRODE GROUND BAR' INSTEAD OF BUILDING STRUCTURAL STEEL IF THE FIRST OVERCURRENT DEVICE FOR THE SEPARATELY DERIVED SYSTEM IS WITHIN 50 FEET OF THE 'MAIN GROUNDING ELECTRODE GROUND BAR'.
- IF THE BUILDING STRUCTURE IS NOT STRUCTURAL STEEL, INSTALL 'MAIN GROUNDING ELECTRODE GROUND BAR EXTENSIONS' AT AN ACCESSIBLE AND VISIBLE LOCATION ADJACENT TO SEPARATELY DERIVED SYSTEMS THAT ARE MORE THAN 50 FEET FROM THE MAIN GROUNDING ELECTRODE GROUND BAR.
- INSTALL A COPPER GROUNDING BAR IN EACH TELECOMMUNICATIONS ROOM. CONNECT TO THE 'MAIN GROUNDING ELECTRODE GROUND BAR' USING 600V INSULATED 4/0 AWG COPPER CABLE AND COMPRESSION SPADE LUGS.
- INSTALL GROUND (NEUTRAL) CONDUCTOR THAT IS NOT LESS THAN THE PHASE CONDUCTOR AMPACITY. IF HIGH-HARMONICS ARE PRESENT MAKE NEUTRAL AMPACITY 200% OF THE PHASE CONDUCTOR.
- INSTALL BONDING CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE OR SEPARATELY-DERIVED SYSTEM PHASE CONDUCTOR SIZE.
- INSTALL IRREVERSIBLE COMPRESSION CONNECTOR WITH TAMPER-PROOF HARDWARE OR INSTALL EXOTHERMIC WELD. REFER SPEC 28 05 26.
- BOND TO METAL PIPING SYSTEMS IN THE AREA SERVED BY THE SEPARATELY DERIVED SYSTEM.
- INSTALL BONDING JUMPER THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE LARGEST SERVICE OR SEPARATELY DERIVED SYSTEM PHASE CONDUCTOR.
- BOND TO INCOMING WATER MAIN USING EXOTHERMIC WELD PROCESS OR OTHER APPROVED MECHANICAL BONDING PROCESS. REFER SPEC 28 05 26.
- TYPICAL EXOTHERMIC WELD PROCESS OR OTHER APPROVED MECHANICAL BONDING PROCESS. REFER SPEC 28 05 26, UNLESS NOTED OTHERWISE.

1 GROUNDING CONNECTION DETAIL
SCALE: NOT TO SCALE



ARCHITECT: SAN ANTONIO PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-9578 F TX Firm BR 1608

ASSOCIATE ARCHITECT: B&A ARCHITECTS 12000 N. LOOP WEST, SUITE 1000 DALLAS, TEXAS 75244-1000

DESIGNER: T&S ARCHITECTS 1100 W. 14TH STREET, SUITE 1000 DENVER, COLORADO 80202

LANDSCAPE: B&A ARCHITECTS 12000 N. LOOP WEST, SUITE 1000 DALLAS, TEXAS 75244-1000

MECHANICAL: LUNY & FRANK ENGINEERING 1100 W. 14TH STREET, SUITE 1000 DENVER, COLORADO 80202



ELECTRICAL: T&S ARCHITECTS 1100 W. 14TH STREET, SUITE 1000 DENVER, COLORADO 80202

INTERIORS: MEAN PROFESSIONALS 12000 N. LOOP WEST, SUITE 1000 DALLAS, TEXAS 75244-1000

STRUCTURE: T&S ARCHITECTS 1100 W. 14TH STREET, SUITE 1000 DENVER, COLORADO 80202



WFAC Black Box Addition PKG 1



CLIENT: Alamo Colleges
DATE: 06/14/2024 PROJECT NUMBER: 230462

DRAWING HISTORY


No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER: 1

ELECTRICAL DETAILS

E-603

ISSUE FOR CONSTRUCTION



SITE PLAN GENERAL NOTES:

1. COORDINATE ROUTING FOR ALL UNDERGROUND ELECTRICAL BRANCH CIRCUITS AND FEEDERS WITH OTHER DISCIPLINES PRIOR TO TRENCHING.
2. UNLESS NOTED OTHERWISE ALL UNDERGROUND CONDUIT SHOWN ON THIS PLAN TO BE MINIMUM 1" IN SIZE.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES CAUSED BY INSTALLATION OF NEW WORK.

SITE PLAN KEYED NOTES:



- 1 EXISTING ELECTRICAL MANHOLE.
- 2 NEW UNDERGROUND EASEMENT FOR NEW PRIMARY POWER FOR UTILITY TRANSFORMER. FIELD VERIFY THAT SPARE CAPACITY IS AVAILABLE.
- 3 NEW 480/277V 750KVA TRANSFORMER SHALL BE PROVIDED FROM ALAMO COLLEGES. CONTRACTOR SHALL COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PROVIDE (1) 1 1/2" CONDUIT FOR POWER.
- 4 NEW UNDERGROUND ROUTE FOR SECONDARY TO MAIN SERVICE DISCONNECT. PROVIDE (2) 3" CONDUITS FOR POWER.
- 5 NEW 480/277V, 40 KW CUMMINS MODEL NUMBER: C40 N6 FOR FIRE PUMP.
- 6 NEW UNDERGROUND PATHWAY FROM GENERATOR TO 2ND FLOOR ATS IN MEZZAINE.
- 7 REROUTED PATHWAY FOR EXISTING UNDERGROUND DUCKSANK WITH 4 EXISTING CONDUITS. CONTRACTOR SHALL VERIFY EXACT PATHWAY OF EXISTING CONDUITS AND FEEDERS SIZES WITHIN EXISTING MANHOLES. CONTRACTOR SHALL COORDINATE NEW PATHWAY WITH ST. PHILLIPS UTILITY FACILITIES TO ENSURE PATHWAY CAN BE Routed.
- 8 RELOCATED CONDENSING UNIT AND ASSOCIATED DISCONNECT. COORDINATE WITH MECHANICAL FOR EXACT LOCATION.
- 9 EXISTING DISTRIBUTION MAIN SERVICE DISCONNECT DP-6 FOR ADJACENT WATSON FINE ARTS BUILDING.
- 10 EXISTING UTILITY TRANSFORMER FOR WATSON FINE ARTS.
- 11 PROPOSED NEW PATHWAY FOR RELOCATED EXISTING CONDUITS FROM DP-6. CONTRACTOR SHALL VERIFY WHERE CONDUITS ARE FED TO.
- 12 NEW LOCATION OF PEDESTRIAN POLES. COORDINATE EXACT LOCATION WITH ARCHITECTURAL DRAWINGS. UTILIZE EXISTING CIRCUIT IF AVAILABLE. IF CIRCUIT ISNT OBTAINABLE CONTRACTOR SHALL UTILIZE NEAREST AVAILABLE SPARE IN PANEL WITH IDENTICAL VOL TAG.



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 1100 N. LOOP WEST SUITE 1000 DALLAS, TEXAS 75242 214-760-1000
LANDSCAPE ARCHITECT	LANDSCAPE 1111 W. 14TH STREET SUITE 1000 DALLAS, TEXAS 75202 214-760-1000
MECHANICAL ENGINEER	LINBY & FRANK ENGINEERING 1111 W. 14TH STREET SUITE 1000 DALLAS, TEXAS 75202 214-760-1000
ELECTRICAL ENGINEER	MEAF PROFESSIONALS 1111 W. 14TH STREET SUITE 1000 DALLAS, TEXAS 75202 214-760-1000



WFAC Black Box Addition PKG 1



CLIENT	Alamo Colleges	
DATE	06/14/2024	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

SITE POWER PLAN

1 SITE POWER PLAN
SCALE: 1" = 20'-0"

PROJECT GENERAL NOTES

- A. ALL EQUIPMENT AND/OR SYSTEMS NOTED ON THE DRAWINGS TO REMAIN SHALL BE INSPECTED AND TESTED ON SITE TO CERTIFY WORKING CONDITION... B. THE PLUMBING WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE APPLICABLE CODES AS WELL AS ALL LOCAL REGULATIONS THAT MAY APPLY... C. ALL PLUMBING WORK SHALL BE COORDINATED WITH ALL OTHER TRADES BEFORE PROCEEDING WITH THE INSTALLATION...

PLUMBING TESTING NOTES

- 1. ALL EQUIPMENT AND/OR SYSTEMS NOTED ON THE DRAWINGS TO REMAIN SHALL BE INSPECTED AND TESTED ON SITE TO CERTIFY WORKING CONDITION... 2. PIPE COVER AND BACKFILLING: A. AFTER HYDROSTATIC TEST, EVENLY BACKFILL ENTIRE TRENCH WIDTH BY HAND PLACING BACKFILL MATERIAL AND HAND TAMPING IN FOUR (4) INCHES COMPACTED LAYERS TO TWELVE (12) INCHES MINIMUM COVER OVER TOP OF JACKET... 3. PRESSURE TEST ALL DOMESTIC WATER PIPING AFTER INSTALLATION AND PRIOR TO BACKFILL OR COVER UP...

PLUMBING ABBREVIATION SCHEDULE

Table with 4 columns: Abbreviation, Description, Abbreviation, Description. Includes items like (A) ITEM NOTED TO BE ABANDONED, (D) ITEM NOTED TO BE DEMOLISHED, (E) EXISTING ITEM, (N) NEW ITEM, (R) ITEM NOTED TO BE RELOCATED, etc.

NOTES: 1. NOT ALL ABBREVIATIONS MAY BE USED ON THESE DRAWINGS.

PLUMBING SYMBOLS LEGEND

Table with 4 columns: Drawings, Details, ABV., Description. Includes symbols for AV ACID VENT, AW ACID WASTE, CA COMPRESSED AIR, CW COLD WATER, (D) DEMOLISHED PIPING OR EQUIPMENT, D CONDENSATE, DSP DRY SPRINKLER, (E) EXISTING PIPING OR EQUIPMENT, F FIRE, G NATURAL GAS, GW GREASE WASTE, HW HOT WATER, HWR HOT WATER RETURN, OD OVERFLOW DRAIN, SD STORM DRAIN, SP SPRINKLER, SS SANITARY SEWER, V VENT, etc.

NOTES: 1. NOT ALL SYMBOLS MAY BE USED ON THESE DRAWINGS.

PLUMBING PIPE MATERIAL SCHEDULE

Table with 3 columns: PIPING SYSTEM, BELOW GRADE, ABOVE GRADE. Includes rows for STORM WATER, SANITARY WASTE, DOMESTIC WATER, NATURAL GAS, FIRE PROTECTION, COMPRESSED AIR.


WATER HAMMER ARRESTER SCHEDULE

Table with 3 columns: PIPE SIZE, CROSS FIXTURE UNITS, PDI STD. Includes rows for 1/2", 3/4", 1", 1-1/4", 1-1/2", 2".

NOTES: 1. AIR CHAMBERS OR SHOCK ARRESTORS SHALL BE PROVIDED TO ALL FIXTURE RUNOUT AND SHALL BE SIZED ACCORDING TO LOCAL PLUMBING CODE (HHS) & PDI. AIR CHAMBERS OR SHOCK ARRESTORS SHALL BE SIZED AND INSTALLED PER MANUFACTURER'S REQUIREMENTS...



SLOPE OF HORIZONTAL DRAINAGE PIPE

Table with 2 columns: PIPE SIZE, MINIMUM SLOPE. Includes rows for 2-1/2" OR LESS (1/4" PER FOOT), 3" TO 6" (1/8" PER FOOT), 8" OR LARGER (1/16" PER FOOT).



KEYNOTES




- P3 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P5 2" VENT UP AND 3" WASTE DOWN.
- P6 2" VENT UP AND 4" WASTE DOWN.
- P8 2" WASTE PIPING DOWN FROM SHOWER DRAIN ABOVE.
- P9 3" WASTE PIPING DOWN FROM FLOOR DRAIN ABOVE.
- P10 4" WASTE PIPING DOWN FROM FLOOR SINK ABOVE.
- P11 4" WASTE DOWN FROM WATER CLOSET ABOVE.
- P12 4" WASTE PIPING DOWN FROM FLOOR CLEAN OUT ABOVE.
- P13 2" WASTE DOWN FROM LAV/SINK ABOVE.
- P14 4" WASTE DOWN FROM WCO ABOVE.
- P17 3" WASTE DOWN FROM MOP SINK.
- P18 2" WASTE DOWN FROM URINAL.
- P20 2" WASTE DOWN FROM WASHING MACHINE BOX.
- P21 2" WASTE DOWN FROM DRINKING FOUNTAIN.
- P28 SANITARY SEWER PIPING STUB-OUT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P29 STORM WATER PIPING STUB-OUT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P34 REFER TO SPECIFICATIONS FOR ESP-1
- P109 FORCED MAIN FROM SUMP PUMP IN CRAWL SPACE.
- P110 SUMP PUMP DISCHARGE CONNECT TO GRATE INLET. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P111 PROVIDE DUPLEX SUMP PUMP MODEL EQUAL TO STANCOR SEW-150 200/3PH 100 GPM @ 20' OF HEAD.
- P112 ELEVATOR DISCHARGE PIPING UP TO OIL SEPARATOR.
- P113 2" FORCED MAIN TO OIL SEPARATOR.
- P115 ELEVATOR SUMP PUMP ESP-1. PUMP TO BE EQUAL TO LIBERTY PUMP 280 50 GPM, 14' HEAD, 1-1/2" DISCHARGE 1/2HP, 115V/1PH.



ARCHITECT PBK Architects, Inc.
 SAN ANTONIO
 601 N. W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1650
 ASSOCIATE ARCHITECT
 DONALD C. RICHARDS
 6152
 07/08/2024
 LEAF ENGINEERS
 F-18672



WFAC Black Box Addition PKG 1
 1801 Main, Luther King Dr.,
 San Antonio, TX 78203
 90%CD - IFR




CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
07/08/2024	230462	
DRAWING HISTORY		
No.	Description	Date
1	CITY COMMENTS	06/05/2024
2	CITY COMMENTS	06/12/2024
3	CITY COMMENTS	06/24/2024
4	CITY COMMENTS	07/08/2024

90%CD - IFR
 BUILDING NUMBER 1


CRAWLSPACE PLUMBING PLAN

PU-101-A

File Path: Autocad Docs://Name CS_230462_Al Philip College WBB AddP23 WFAC - Blackbox Addition - A03.rvt
 CHECKED BY: Checker
 DRAWN BY: Author
 Plot Stamp: 7/8/2024 7:29:33 AM



1 1ST LEVEL ENLARGED PLUMBING PLAN - AREA C
SCALE: 1/4" = 1'-0"



2 1ST LEVEL ENLARGED PLUMBING PLAN - AREA D
SCALE: 1/4" = 1'-0"

KEYNOTES

- P3 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P6 2" VENT UP AND 4" WASTE DOWN.
- P10 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P39 ROOF DRAIN PIPING DOWN TO BELOW FLOOR. SIZE AS NOTED.
- P45 3/4" COLD WATER, 3/4" HOT WATER DOWN AND 2" VENT UP.
- P46 3/4" COLD WATER DOWN AND 2" VENT UP.
- P48 3/4" COLD WATER AND 3/4" HOT WATER DOWN TO SHOWER VALVE.
- P49 1 1/4" COLD WATER DOWN AND 2" VENT UP.
- P71 HOT WATER DOWN IN CHASE / WALL SIZE AS NOTED.
- P73 PROVIDE BALANCING VALVE.
- P114 PROVIDE ELEVATOR SLUMP SYSTEM EQUAL TO PARK ELYC-100 SEPARATOR MODEL ESC-100 50 GPM FLOW RATE 100 GALLON CAPACITY.






ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N. W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P TX Firm SR 1659
ASSOCIATE ARCHITECT	W.A. ARCHITECTS 1710 S. W. 19th St. San Antonio, TX 78224
ENGINEER	LEE 1710 S. W. 19th St. San Antonio, TX 78224
MECHANICAL ENGINEER	LEE 1710 S. W. 19th St. San Antonio, TX 78224
ELECTRICAL ENGINEER	LEE 1710 S. W. 19th St. San Antonio, TX 78224
PLUMBING ENGINEER	LEE 1710 S. W. 19th St. San Antonio, TX 78224
MECHANICAL PROFESSIONALS	LEE 1710 S. W. 19th St. San Antonio, TX 78224
ELECTRICAL PROFESSIONALS	LEE 1710 S. W. 19th St. San Antonio, TX 78224
PLUMBING PROFESSIONALS	LEE 1710 S. W. 19th St. San Antonio, TX 78224



WFAC Black Box Addition PKG 1


1801 Main, Luber King Dr.,
San Antonio, TX 78203
90%CD - IFR




CLIENT		Alamo Colleges
DATE	07/08/2024	PROJECT NUMBER
DRAWING HISTORY		230462
No.	Description	Date
4	CITY COMMENTS	07/08/2024
90%CD - IFR		
BUILDING NUMBER	1	

PLUMBING ENLARGED PLAN


P-401




10 COMPRESSED AIR OUTLET DETAIL
SCALE: NOT TO SCALE



7 EMERGENCY SHOWER/EYEWASH DETAIL
SCALE: NOT TO SCALE




4 ELECTRIC WATER HEATER PIPING
SCALE: N.T.S.




MAXIMUM PIPING / TUBING SUPPORT SPACING																	
NOM. SIZE	3/4"	1"	1 1/4"	1 1/2"	2"	3"	4"	5"	6"	8"	10"	12"	14"	16"	18"	20"	24"
PIPING	7"	7"	7"	9"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"
TUBING	5"	6"	6"	6"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"

NOTE: FOR TRAPEZE HANGER TAKE SPACING OF SMALLEST SIZE ON TRAPEZE.


1 ADJUSTABLE CLEVIS PIPE HANGER DETAIL
SCALE: NOT TO SCALE




11 WALL HYDRANT DETAIL
SCALE: NOT TO SCALE



8 SHOCK ARRESTOR DETAIL
SCALE: NOT TO SCALE




5 WASHER / DRAIN BOX CONNECTION DETAIL
SCALE: NOT TO SCALE




MAXIMUM PIPING / TUBING SUPPORT SPACING																	
NOM. SIZE	3/4"	1"	1 1/4"	1 1/2"	2"	3"	4"	5"	6"	8"	10"	12"	14"	16"	18"	20"	24"
PIPING	7"	7"	7"	9"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"
TUBING	5"	6"	6"	6"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"

NOTE: FOR TRAPEZE HANGER TAKE SPACING OF SMALLEST SIZE ON TRAPEZE.


2 ADJUSTABLE ROLLER PIPE HANGER DETAIL
SCALE: NOT TO SCALE




12 WALL HYDRANT DETAIL
SCALE: NOT TO SCALE



9 AIR COMPRESSOR PIPING DETAIL
SCALE: NOT TO SCALE



6 BACKFLOW PREVENTER MOUNTING DETAIL
SCALE: NOT TO SCALE



MAXIMUM PIPING / TUBING SUPPORT SPACING																	
NOM. SIZE	3/4"	1"	1 1/4"	1 1/2"	2"	3"	4"	5"	6"	8"	10"	12"	14"	16"	18"	20"	24"
PIPING	7"	7"	7"	9"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"
TUBING	5"	6"	6"	6"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"

NOTE: FOR TRAPEZE HANGER TAKE SPACING OF SMALLEST SIZE ON TRAPEZE.



3 TRAPEZE PIPE HANGER DETAIL
SCALE: NOT TO SCALE



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-0578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	MAX ARCHITECTS
1101 S. W. Loop West Suite 100 San Antonio, TX 78205 210-340-0992	
LANDSCAPE ARCHITECT	LANDSCAPE
1111 S. W. Loop West Suite 100 San Antonio, TX 78205 210-340-0992	
MECHANICAL ENGINEER	LUNY & FRANK ENGINEERING
1111 S. W. Loop West Suite 100 San Antonio, TX 78205 210-340-0992	
ELECTRICAL ENGINEER	MEYER
1111 S. W. Loop West Suite 100 San Antonio, TX 78205 210-340-0992	
PLUMBING ENGINEER	MEYER
1111 S. W. Loop West Suite 100 San Antonio, TX 78205 210-340-0992	




WFAC Black Box Addition PKG 1




CLIENT		Alamo Colleges	
DATE	06/14/2024	PROJECT NUMBER	230462
DRAWING HISTORY			
No.	Description	Date	

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1


PLUMBING DETAILS




4 ELEVATOR OIL INTERCEPTOR SUMP PIT DETAIL
SCALE: NOT TO SCALE



1 DOMESTIC COLD WATER ENTRY
SCALE: N.T.S.




2 FIRE PUMP
SCALE: N.T.S.



3 DUPLIX PACKAGE PUMPING SYSTEM
SCALE: N.T.S.

P-602
 PLUMBING DETAILS
 FOR BLUEBEAM LABELING OCR:
 File Path: Autocad Dcs://Name CS_230462_A1 Philip College WBB AddP23 WFAC - Blackbox Addition - A03.rvt
 CHECKED BY: [Blank]
 CHECKER: [Blank]
 DRAWN BY: [Blank]
 AUTHOR: [Blank]
 Plot Stamp:
 7/8/2024 7:29:34 AM

ISSUE FOR CONSTRUCTION



1 SITE TECHNOLOGY PLAN
 SCALE: 1" = 30'-0"

TECHNOLOGY KEYNOTES

- TS1 INDICATES THE APPROXIMATE LOCATION OF THE NEW BUILDING IDF. CONDUITS SHALL BE STUB EVENTLY AT +8 A.F.F TO ENTER THE NEW MDF/IDF
- TS3 CONTRACTOR TO INSTALL TWO (2) FOUR INCH (4") CONDUIT WITH A PULLING LINE FROM THIS MANHOLE ALL THE WAY TO THE NEW IDF ROUTED AT 4 B.F.G. PROVIDE TWO (2) 3-CELL MAXCELL INNERDUCT IN EACH CONDUIT. THE UNDERGROUND CONDUIT PATHWAY WILL BE INSTALLED BY THE DIV 26 CONTRACTOR.
- TS4 INDICATES THE APPROXIMATE LOCATION OF AN EXISTING MANHOLE
- TS5 INDICATES THE APPROXIMATE LOCATION OF AN EXISTING CONDUIT PATHWAY TO BE REMOVED CONTRACTOR SHALL PULL BACK EXISTING FIBER FROM THE EXISTING MANHOLE ALL THE WAY BACK TO THE PREVIOUS BOX. FIBER TO BE RE-USED IF POSSIBLE. CONTRACTOR WILL RE-ROUTE THE EXISTING FIBER AND FUSE SPLICE AT THE SAME BOX IT WAS PULLED FROM THE BEGINNING JUST FROM A DIFFERENT PATHWAY. CONTRACTOR SHALL PAY FOR ANY DAMAGE TO EXISTING FIBER.
- TS6 INDICATES THE APPROXIMATE LOCATION FOR THE NEW PATHWAY FOR THE EXISTING FIBER TO BE RE-ROUTED TO MAINTAIN THE SERVICE UP AND RUNNING. CONTRACTOR TO FIELD VERIFY THE AMOUNT OF CONDUIT NEEDED FOR THIS NEW ROUTE TO WORK AS THE PREVIOUS.
- TS8 INDICATES THE APPROXIMATE LOCATION OF THE EXISTING CAMPUS MDF. CONDUITS SHALL BE STUBBED EVENTLY AT +8 A.F.F TO ENTER THE MDF/IDF.
- TS9 CONTRACTOR TO PULL A NEW ONE (1) 24-STRAND SINGLE MODE FIBER OUTDOOR/ARMORED-RATED FROM THE EXISTING CAMPUS MDF INTO THE NEW BLACK BOX BUILDING IDF. PROVIDE TWO (2) 3-CELL MAXCELL INNERDUCT IN EACH CONDUIT.
- TS10 CONTRACTOR TO FIELD VERIFY THE EXISTING PATHWAY AND REROUTE THE EXISTING FIBER INTO THE NEW PATHWAY PRIOR TO ANY CONSTRUCTION TO MAINTAIN THE NETWORK ALIVE. CONTRACTOR TO LABEL ALL SPOOLS IN THE MANHOLE ACCORDING TO ACC STANDARDS AND REMOVED ANY NON-WORKING CABLING ALL THE WAY TO THE CAMPUS MDF PATHWAY.
- TS11 CONTRACTOR TO REMOVE ALL NON-WORKING LOW VOLTAGE CABLE ALL THE WAY TO THE CAMPUS MDF DURING THE NEW FIBER PULLING FOR THIS PROJECT.





ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-5578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 200 CELESTER LANDSCAPE SITES AND DESIGN 1111 W. 40th Street San Antonio, TX 78204
MECHANICAL ENGINEER	LUNDY & FRANK ENGINEERING 1111 W. 40th Street San Antonio, TX 78204
ELECTRICAL ENGINEER	ME 1111 W. 40th Street San Antonio, TX 78204
PLUMBING ENGINEER	MEAN PROFESSIONALS 1111 W. 40th Street San Antonio, TX 78204
MECHANICAL ENGINEER	MEAN 1111 W. 40th Street San Antonio, TX 78204



WFAC Black Box Addition PKG 1

1801 Mainfr, Luther King Dr.,
 San Antonio, TX 78203
 ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
2024/06/14		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
 BUILDING NUMBER 1

SITE TECHNOLOGY PLAN

TS-101